

## GENERAL NOTES

G.N.-100  
 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER  
 AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT.  
 WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-442B -- PATCHING SCHEDULES  
 THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT  
 THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION  
 OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES  
 OF THE FULL-DEPTH PATCHES MAY OCCUR.

G.N. -780 SPECIAL  
 PAINT PAVEMENT MARKINGS SHALL BE APPLIED UPON COMPLETION  
 OF THE PATCH WORK. PAINT PAVEMENT MARKINGS SHALL COINCIDE  
 WITH THE EXISTING PAVEMENT MARKINGS. PAINT PAVEMENT MARKINGS  
 SHALL BE LIMITED TO THE PATCH LENGTH AT EACH PATCH LOCATION.  
 PAINT PAVEMENT MARKINGS SHALL NOT BE APPLIED CONTINUOUSLY  
 THROUGH THE PROJECT BETWEEN PATCH LOCATIONS.

G.N.-1004.01  
 COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER  
 COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD  
 SPECIFICATIONS.

NO COMMITMENTS

FILE NAME = c:\projects\4570705\70705plans.dgn	USER NAME = collier-bw	DESIGNED - RTB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.I. RTE. 74	SECTION (92-1111)	COUNTY VERMILION	TOTAL SHEETS 17	SHEET NO. 3
PLOT SCALE = 100.0000' / IN.	CHECKED -	DRAWN - JRP	REVISED -	SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 70705 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		
PLOT DATE = 3/13/2008	DATE - 12-07	CHECKED -	REVISED -							