GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-440B

THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS AND/OR COMBINATION CURB AND GUTTERS THAT ARE FOUND SUITABLE FOR REUSE SHALL BE CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY EXISTING TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-442B -- PATCHING SCHEDULES
THE PATCHING SCHEDULES INCLUDED IN THE PLANS
REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME
OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN
LOCATION AND SIZES OF BOTH FULL-DEPTH AND
PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N. -780 SPECIAL

PAINT PAVEMENT MARKINGS SHALL BE APPLIED UPON COMPLETION OF THE PATCH WORK. PAINT PAVEMENT MARKINGS SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. PAINT PAVEMENT MARKINGS SHALL BE LIMITED TO THE PATCH LENGTH AT EACH PATCH LOCATION. PAINT PAVEMENT MARKINGS SHALL NOT BE APPLIED CONTINUOUSLY THROUGH THE PROJECT BETWEEN PATCH LOCATIONS.

ESTIMATED QUANTITIES:

YELLOW:

138.0 LIN. FT. - PAINT PAVEMENT MARKING, LINE 4"

WHITE

324.0 LIN. FT. - PAINT PAVEMENT MARKING, LINE 4" 123.0 LIN. FT. - PAINT PAVEMENT MARKING, LINE 6"

TOTALS:

462.0 LIN. FT. - PAINT PAVEMENT MARKING, LINE 4" 123.0 LIN. FT. - PAINT PAVEMENT MARKING, LINE 6"

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

THERE ARE NO COMMITMENTS FOR THE CONTRACT.

FILE NAME :	USER NAME = weger ja	DESIGNED -	REVISED -	
c:\projects\d570725\70637 text.dgn		DRAWN -	REVISED -	
	PLOT SCALE = 40.0000 '/ (N.	CHECKED -	REVISED -	1
:	PLOT DATE : 3/25/2008	DATE -	REVISED -	

STATE	0F	ILLINOIS
DEPARTMENT	OF 1	TRANSPORTATION

SCALE:

GENERAL NOTES /COMMITMENTS					F.A.P. RTE.	St	COUNTY	TOTAL	SHEET NO.			
					730	D5 PATC	HING 2008-6	MCLEAN	14	3		
					1			CONTRACT	NO.	70725		
	SHEET	NO.	OF	SHEETS	STA.	TO STA.	FED. RO	DAD DIST. NO.	ILLINOIS FED. AI	D PROJECT		