

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-9)RS-6r (G)Z	SANGAMON	425	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

FAI 72 IM
FAU 8071 ACM
FAU 8071
FAU 8071
80% FED. 10% STATE
FAU 8071 ACM

LOCATION OF WORK	INTERCHANGE AND I-72	MACARTHUR BLVD (NORTH LEG)	MACARTHUR BLVD (NORTH LEG)	EXTRA WORK LEGACY POINTE DEVELOPMENT	BIKE TRAIL INTERURBAN
	90% FED 10% STATE	URBAN 80% FED 20% STATE	LOCAL 100% LOCAL	LOCAL 100% LOCAL	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				Y047
				I000-2A	I000-2A	I000-2A	I000-2A	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1075	1075				
60218500	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2		1	1		
60220200	MANHOLES, TYPE A, 4' -DIAMETER	EACH	2		1	1		
60222900	MANHOLES, TYPE A, 5' -DIAMETER	EACH	4		2	2		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	4	4				
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	109	11	30	30	38	
60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	6		3	3		
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	45		13.7	13.7	17.6	
60240330	INLETS, TYPE B, TYPE 37 GRATE	EACH	1		0.5	0.5		
60240400	INLETS, TYPE B, SPECIAL, WITH FRAME AND GRATE	EACH	1		0.5	0.5		
60247900	JUNCTION CHAMBER, SPECIAL	EACH	1					1
60403200	GRATES, TYPE 37	EACH	6		3	3		
60405900	GRATES AND COVERS, TYPE 2B	EACH	6	6				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	20.9	20.9				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 12	FOOT	2569.5	510.0	626.8	626.8	805.9	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 18	FOOT	28392	12005.5	8193.25	8193.25		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	12422	3878.5	4271.75	4271.75		
60608509	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2. 18	FOOT	129.5	129.5				
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6. 06	FOOT	350	82.0	81.5	81.5	105.0	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6. 24	FOOT	334	113.0	67.3	67.3	86.4	
60610900	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6. 24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	307.5		93.6	93.6	120.3	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	30375	13136.0	5246.7	5246.7	6745.6	
60619600	CONCRETE MEDIAN, TYPE SB-6. 12	SQ FT	1859		565.8	565.8	727.4	
60620300	CONCRETE MEDIAN, TYPE SB-6. 24 (SPECIAL)	SQ FT	10548	137.0	3168.6	3168.6	4073.8	
60622800	CONCRETE MEDIAN, TYPE SM-6. 12	SQ FT	1304		397	397	510	
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	14	13	0.5	0.5		
60900150	TYPE B INLET BOX, STANDARD 609006 (SPECIAL)	EACH	2		1	1		
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	3	3				
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	6	4	1	1		
60900320	TYPE D INLET BOX, STANDARD 609006 (SPECIAL)	EACH	1		0.5	0.5		

- PAY ITEM REQUIRES A SPECIAL PROVISION

PLT DATE = 11/14/2008 BY JRS/BJM
FILE NAME = C:\p\11-2008\11-14-08\11-14-08.dgn
PLOT SCALE = 1/8"=1'-0" / IN.
USER NAME = jrs/BJM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 72 (I-72)
SECTION (84-9)RS-6r (G)Z
SANGAMON COUNTY
SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____