CONTRACT #72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	68
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6; (G)Z *

CONCRETE CURB, CURB AND GUTTER, MEDIAN AND BRIDGE APPROACH PAVEMENT SCHEDULE

LOCATION			BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT	BRIDGE APPROACH PAVEMENT (SPECIAL)	APPROACH PAVEMENT SPECIAL	CLASS SI CONCRETE (OUTLET)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB-6.12	CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL)	CONCRETE MEDIAN, TYPE SM-6.12
			SQ YD	SQ YD	SQ YD	SQ YD	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ FT	SQ FT
BEGIN STATION	**END STATION**	**OFFSET**																
53+55.00	56+60.00	R		89					304.5									
56+65.00		RT		10														
56+70.00	57+47.63	R		45					154.0									
57+34.90	57+46.80	L		4									12.0					
		SUBTOTAL	**179**	**1106**			**2.1**		**2899.0**	**8.0**			**12.0**					
RAMP D																		
40+53.00	46+65.20	L		178					608.5									
40+53.80	40+69.10	R		6									19.0					
40+59.00	41+83.00	R		49					168.0									
41+88.00		RT		10														
41+93.00	46+65.20	R		139					472.5									
46+65.20	46+73.20	L		3						8.0								
46+65.20	46+73.20	R		3						8.0								
47+00.00		LT		10			2.1											
47+00.00		RT		10			2.1											
		SUBTOTAL		**408**			**4.2**		**1249.0**	**16.0**			**19.0**					
INTERURBAN TRAIL																		
24+73.00	24+88.00			17		17												
27+17.00	27+32.00			17		17												
		SUBTOTAL		**34**		**34**												
RECREATION DRIVE																		
100+53.80	101+04.50	L		18					63.0									
100+83.70	101+29.72	RT		21			4.6											
101+04.50	101+62.10	LT		25			3.7											
		SUBTOTAL		**64**			**8.3**		**63.0**									
LINCOLNSHIRE BOULEVARD																		
178+50.00	178+99.93			33												296.0		
179+16.75	179+43.66	L		5								26.5						
179+21.48	179+40.16	R		5								25.5						
179+21.48	179+44.80	R		17										28.5				
179+28.02	179+45.87	L		7									21.0					
180+53.76	180+74.32	R		8									24.0					
180+54.44	180+84.40	L		22										36.0				
180+55.28	180+74.32	R		5								29.5						
180+55.67	181+47.20	L		60					204.0									
180+58.60	180+84.40	L		6								33.0						
180+62.62	182+18.96	R		53					179.5									
180+67.24	182+51.59	R		34				185.5										
180+67.42	182+51.59	R		34				184.5										
181+47.20	183+41.16	L		57					194.0									
182+18.96	183+36.46	R		34					117.5									
182+51.59	183+56.70			70												627.0		
183+36.46	183+94.39	R		21					73.0									
183+41.16	183+79.19	L		20					66.5									
		SUBTOTAL		**491**				**370.0**	**834.5**			**114.5**	**45.0**	**64.5**		**923.0**		
CENTRE STREET																		
10+10.90	13+04.80	R		93					316.0									
10+14.50	13+26.20	L		105					357.0									
		SUBTOTAL		**198**					**673.0**									
CENTER ACCESS																		
700+55.54	700+69.96	R		6									17.5					
700+56.28	700+79.23	L		5								27.5						
700+57.99	700+69.96	R		4								20.5						
700+77.89	701+73.00			61														553.0
800+53.02	700+79.23	L		21										32.5				
		SUBTOTAL		**97**								**48.0**	**17.5**	**32.5**				**553.0**
LINDBERGH																		
600+47.07	600+72.15	L		19										31.0				
600+50.14	600+63.59	R		6									16.5					
600+50.55	600+72.15	L		5								26.5						
600+53.00	600+63.59	R		3								18.0						
600+82.29	601+05.00			12														111.0
		SUBTOTAL		**45**								**44.5**	**16.5**	**31.0**				**111.0**
WESTCHESTER																		
503+05.03	504+13.69			71														640.0
504+24.91	504+48.25	R		4										30.0				
504+24.91	504+41.60	R		18								23.0						
504+31.12	504+57.12	L		9								38.0						
504+31.12	504+55.47	L		7									28.0					
		SUBTOTAL		**109**								**61.0**	**28.0**	**30.0**				**640.0**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES -8
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6; (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE Mar-20-2008 07:47:21AM CHECKED BY MH

© Copyright Hanson Professional Services Inc. 2008

HANSON

Mar-20-2008 07:47:21AM
$FILE$

LAYOUT	CLG	09/17/07
DRAWN	CLG	09/17/07
REVIEWED	JMM	03/12/08