

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	78
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9) RS-6; (G)Z *				

SEEDING SCHEDULE

LOCATION	SEEDING, CLASS 2	SEEDING, CLASS 3	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MOWING	MULCH, METHOD 2	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING
	ACRE	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	ACRE	SQ YD	UNIT
BEGIN STATION											
END STATION											
OFFSET											
MACARTHUR BOULEVARD											
26+50.00	784+00.00	RAMP A / MAC									
34+00.00	798+08.49	RAMP C / MAC									
769+60.00	784+00.00		1.00								
771+43.35	785+73.80	MACARTHUR MEDIAN									
784+00.00	44+00.00	RAMP B / MAC									
798+08.49	48+00.00	RAMP D / MAC									
798+08.49	809+00.00										
784+00.00	809+00.00										
802+14.78	816+17.14										
809+00.00	817+00.00		1.00								
817+00.00	840+00.00		1.50								
822+95.69	872+90.00	MACARTHUR MEDIAN									
840+00.00	877+00.00		3.00								
STAGING AREA NORTH OF RAMP C AND BIKE TRAIL			5.00								
SUBTOTAL			11.50	3.75	1223.0	1223.0	1223.0	28.5	11.00	24.50	8064
RAMP A											
10+00.00	26+50.00		0.75								
10+00.00	30+54.00										
SUBTOTAL			0.75		90.0	90.0	90.0	2.0	0.75	2.00	
RAMP B											
22+00.00	50+41.36										
30+00.00	34+00.00										
44+00.00	50+41.36		0.25								
SUBTOTAL			0.25		112.5	112.5	112.5	2.5	0.25	2.50	
RAMP C											
30+00.00	34+00.00		1.00								
30+00.00	56+50.00										
SUBTOTAL			1.00		157.5	157.5	157.5	3.5	1.00	3.50	
RAMP D											
42+00.00	67+51.59										
48+00.00	67+51.59		0.75								
SUBTOTAL			0.75		112.5	112.5	112.5	2.5	0.75	2.50	
RECREATION DRIVE											
ROADWAY TOTAL			1.00		90.0	90.0	90.0	2.0	1.00	2.00	
SUBTOTAL			1.00		90.0	90.0	90.0	2.0	1.00	2.00	
LINCOLNSHIRE BOULEVARD											
ROADWAY TOTAL			0.25		23.0	23.0	23.0	0.5	0.25	0.50	
SUBTOTAL			0.25		23.0	23.0	23.0	0.5	0.25	0.50	
CENTRE STREET											
ROADWAY TOTAL			0.25		23.0	23.0	23.0	0.5	0.25	0.50	
SUBTOTAL			0.25		23.0	23.0	23.0	0.5	0.25	0.50	
INTERURBAN TRAIL											
10+00.00	24+00.00		0.75								
15+00.00	24+00.00		0.25								
28+00.00	36+00.00		0.50								
38+00.00	84+00.00		2.25								
PARKING LOT			0.25		22.5	22.5	22.5	0.5	0.25	0.50	
SUBTOTAL			0.50	3.50	360.0	360.0	360.0	8.0	0.50	8.00	
PROJECT TOTAL											
CITY SECTION					14.50						
STATE SECTION					8.50						
SUBTOTAL					23.00						
TOTAL			16.25	7.25	23.00	2191.5	2191.5	2191.5	50.0	15.75	46.00
										8064	403.2



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES -18
 FAI-72, MACARTHUR BLVD
 SECTION
 (84-9) RS-6; (G)Z
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT.
 HORIZ.
 DATE Mar-20-2008 07:47:42AM
 DRAWN BY CLG
 CHECKED BY MH