CONTRACT #72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	84
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6; (G)Z *

DRAINAGE STRUCTURE SCHEDULE – 1

#	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L(OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE A, SPCL F & G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, SPCL F & G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	TYPE A, 7' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME AND LID TY 1 CL	FRAME AND GRATE TY 3	GRATE AND COVER TY 2B	GRATE TY 37	PRC FLARED END SECT: 12"	18"	24"	36"	72"	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HVY DUTY EXCELSIOR BLANKET	COMMENTS
1	MAC BLVD	770+93.50	7.30	L	600.34		1																																													
2	MAC BLVD	771+13.00	44.50	L	599.49															1																																
~~3~~	~~MAC BLVD~~	~~771+13.00~~	~~68.00~~	~~L~~	~~595.05~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
4	MAC BLVD	770+93.50	0.99	R	600.43		1																																													
5	MAC BLVD	770+93.50	44.50	R	599.40																1																																
~~6~~	~~MAC BLVD~~	~~770+00.36~~	~~69.00~~	~~R~~	~~594.5~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	X	
7	MAC BLVD	775+50.00	7.30	L	606.62		1																																													
8	MAC BLVD	775+50.00	44.50	L	605.69															1																																
~~9~~	~~MAC BLVD~~	~~775+50.00~~	~~86.00~~	~~L~~	~~598.8~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
10	MAC BLVD	775+50.00	7.30	R	606.62		1																																													
11	MAC BLVD	775+50.00	44.50	R	605.69																1																																
~~12~~	~~MAC BLVD~~	~~775+50.00~~	~~86.00~~	~~R~~	~~598.8~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
13	MAC BLVD	780+50.00	7.30	L	616.62		1																																													
14	MAC BLVD	780+50.00	44.50	L	615.69															1																																
~~15~~	~~MAC BLVD~~	~~780+50.00~~	~~118.00~~	~~L~~	~~598.8~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
16	MAC BLVD	780+50.00	7.30	R	616.62		1																																													
17	MAC BLVD	780+50.00	44.50	R	615.69																1																																
~~18~~	~~MAC BLVD~~	~~780+50.00~~	~~118.00~~	~~R~~	~~598.8~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
19	MAC BLVD	785+50.00	15.27	L	626.62		1																																													
20	MAC BLVD	785+50.00	52.47	L	625.69																1																																
~~21~~	~~MAC BLVD~~	~~785+50.00~~	~~87.00~~	~~L~~	~~610.3~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
22	MAC BLVD	785+50.00	15.27	R	626.62		1																																													
23	MAC BLVD	785+50.00	58.47	R	625.69								1																																							
~~24~~	~~MAC BLVD~~	~~785+50.00~~	~~92.00~~	~~R~~	~~610.3~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
25	RAMP A	28+57.00	20.05	R	626.52														1																																	
~~26~~	~~RAMP A~~	~~28+57.00~~	~~63.00~~	~~R~~	~~610.63~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
27	RAMP B	21+88.50	8.06	R	626.48														1																																	
~~28~~	~~RAMP B~~	~~21+88.50~~	~~41.00~~	~~R~~	~~619.02~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
29	MAC BLVD	788+15.00	53.00	R	630.99															1																																
~~30~~	~~MAC BLVD~~	~~788+24.50~~	~~101.00~~	~~R~~	~~614.25~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
31	MAC BLVD	788+12.00	53.00	L	630.93															1																																
~~32~~	~~MAC BLVD~~	~~788+48.00~~	~~92.00~~	~~L~~	~~614.3~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
33	MAC BLVD	791+45.50	53.42	L	637.64												1																																			
~~34~~	~~MAC BLVD~~	~~791+45.50~~	~~140.00~~	~~L~~	~~602~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
35	MAC BLVD	791+57.00	53.42	R	637.83												1																																			
~~36~~	~~MAC BLVD~~	~~791+57.00~~	~~148.00~~	~~R~~	~~598.5~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
37	MAC BLVD	794+04.00	53.42	L	640.69												1																																			
~~38~~	~~MAC BLVD~~	~~794+04.00~~	~~150.00~~	~~L~~	~~598.5~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
39	MAC BLVD	794+15.50	53.42	R	640.77												1																																			
~~40~~	~~MAC BLVD~~	~~794+23.00~~	~~150.00~~	~~R~~	~~603~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
41	RAMP D	41+88.00	8.07	R	638.38														1																																	
~~42~~	~~RAMP D~~	~~41+88.00~~	~~49.00~~	~~R~~	~~619.27~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	
43	RAMP C	56+65.00	20.23	R	639.18														1																																	
~~44~~	~~RAMP C~~	~~56+25.00~~	~~86.00~~	~~R~~	~~618.5~~	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	~~1~~	X	X	X	X	X	X	X	~~18~~	

NOTE:
"X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -1
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6; (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. — DRAWN BY CLG
DATE Mar-20-2008 08:58:42AM — CHECKED BY JWM

LAYOUT	BLW	01/28/08
DRAWN	CLG	01/28/08
REVIEWED	BLW	01/28/08

Mar-20-2008 08:58:42AM
#FILE#

HANSON

© Copyright Hanson Professional Services Inc. 2006