CONTRACT #72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	87
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6; (G)Z *

DRAINAGE STRUCTURE SCHEDULE – 4

#	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L(OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE A, SPCL F & G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, SPCL F & G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	TYPE A, 7' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME AND LID TY 1 CL	FRAME AND GRATE TY 3	GRATE AND COVER TY 2B	GRATE TY 37	PRC FLARED END SECT: 12"	18"	24"	36"	72"	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HVY DUTY EXCELSIOR BLANKET	COMMENTS
~~135~~	~~N/A~~																																																				
~~136~~	~~N/A~~																																																				
~~137~~	~~N/A~~																																																				
~~138~~	~~N/A~~																																																				
~~139~~	~~N/A~~																																																				
~~140~~	~~N/A~~																																																				
~~141~~	~~N/A~~																																																				
~~142~~	~~N/A~~																																																				
144	MAC BLVD	837+20.00	57.84	L	609.03					1																																											
145	MAC BLVD	837+20.00	7.30	L	609.96					1																																											
147	MAC BLVD	837+20.00	46.20	R	609.27					1																																											
~~148~~	~~MAC BLVD~~	~~837+20.00~~	~~70.00~~	~~R~~	~~606.74~~																									1								1													
149	MAC BLVD	840+80.00	46.20	L	609.34		1																																														
152	MAC BLVD	840+80.00	46.20	R	609.34		1																																														
~~153~~	~~MAC BLVD~~	~~840+80.00~~	~~65.75~~	~~R~~	~~*~~																																1															
~~154~~	~~MAC BLVD~~	~~840+10.00~~	~~65.00~~	~~R~~	~~607.83~~																1																															
~~155~~	~~N/A~~																																																				CONNECT TO ~~EXISTING STORM~~ SEWER
156	MAC BLVD	842+00.00	62.36	L	608.65		1																																														
157	MAC BLVD	842+00.00	7.30	L	609.67		1																																														
159	MAC BLVD	842+00.00	46.20	R	608.98		1																																														
~~160~~	~~N/A~~																																																				
161	MAC BLVD	844+75.00	58.20	L	607.91		1																																														
162	MAC BLVD	844+75.00	7.30	L	608.84		1																																														
163	MAC BLVD	844+75.00	7.30	R	608.84		1																																														
164	MAC BLVD	844+75.00	46.20	R	608.15		1																																														
~~165~~	~~MAC BLVD~~	~~844+75.00~~	~~65.60~~	~~R~~	~~*~~																														1																
166	MAC BLVD	846+30.00	58.20	L	607.45		1																																														
167	MAC BLVD	846+30.00	7.30	L	608.38		1																																														
168	MAC BLVD	846+30.00	7.30	R	608.38		1																																														
169	MAC BLVD	846+30.00	46.20	R	607.69		1																																														
~~170~~	~~MAC BLVD~~	~~846+30.00~~	~~69.50~~	~~R~~	~~*~~																														1																
~~171~~	~~MAC BLVD~~	~~847+85.00~~	~~90.60~~	~~L~~	~~604.12~~						1																																								
172	MAC BLVD	847+85.00	55.90	L	607.03					1																																											
173	MAC BLVD	847+85.00	7.30	L	607.91					1																																											
174	MAC BLVD	847+85.00	7.30	R	607.91					1																																											
175	MAC BLVD	847+85.00	46.20	R	607.22					1																																											
~~176~~	~~MAC BLVD~~	~~847+85.00~~	~~73.40~~	~~R~~	~~604.12~~																									1										1											
177	MAC BLVD	849+40.00	46.60	L	606.75		1																																														
178	MAC BLVD	849+40.00	7.30	L	607.45		1																																														
180	MAC BLVD	849+40.00	46.20	R	606.76		1																																														
~~181~~	~~MAC BLVD~~	~~849+40.00~~	~~73.00~~	~~R~~	~~*~~																														1																
182	MAC BLVD	850+95.00	47.60	L	606.26					1																																											
183	MAC BLVD	850+95.00	7.30	L	606.98					1																																											
185	MAC BLVD	850+95.00	46.20	R	606.29					1																																											

NOTE:
"X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -4
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6; (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE Mar-20-2008 08:58:58AM CHECKED BY JWM

LAYOUT	BLW	01/28/08
DRAWN	CLG	01/28/08
REVIEWED	BLW	01/28/08

Mar-20-2008 08:58:58AM
#FILE#

© Copyright Hanson Professional Services Inc. 2006
HANSON