


FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	98
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9) RS-6; (G)Z *				

STORM SEWER SCHEDULE - 3

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A													TRENCHLESS PIPE INSTALLATION 72" STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS
				TYPE 1			TYPE 2				TYPE 3		TY 5	TYPE 6						
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"	18"				
196	599.08	402	599.50																	
197	608.25	192	599.92																	
193	602.49	194	602.19	50																
194	602.19	195	601.99	14																
195	601.99	196	601.49	38																
196	601.49	197	601.33	5																
197	599.66	202	599.95																	
198	602.02	199	601.72	50																
199	601.72	200	601.52	14																
200	601.52	201	601.02	38																
201	601.02	202	600.88	5																
202	599.95	208	594.24																	
203	599.51	204	599.52																	
204	599.52	205	597.80																	
205	597.80	206	597.06																	
206	597.06	207	596.41																	
207	596.41	208	595.91																	
208	594.24	248	594.41																	
209	600.87	210	600.57	50																
210	600.57	211	600.48	14																
211	600.48	212	600.27	34																
212	600.27	213	600.11	5																
213	594.41	218	594.53																	
214	600.71	216	600.64	9																
215	600.10	217	600.08	9																
216	600.64	363	600.36	47																
217	600.08	218	599.92	4																
218	594.53	221	594.71																	
219	601.22	365	600.32	48																
220	600.32	221	600.06	5																
221	594.71	225	594.95																	
222	597.91	228	597.07																	
223	597.07	267	596.34																	
224	595.91	225	594.95																	
225	594.95	226	595.19																	
226	602.06	369	601.76	32																
227	601.26	228	601.18	5																
228	595.41	291	595.21																	
229	596.41	374	596.26																	
230	596.01	201	595.21																	
231	595.21	297	599.03																	
232	600.01	208	599.01																	
233	599.91	202	599.41																	
234	599.01	205	599.25																	
235	596.25	240	599.53																	
236	601.26	237	601.18	5																
237	596.03	205	596.25																	
238	600.38	372	600.43	41																
239	600.13	240	600.05	5																
240	596.33	244	596.51																	

NOTE:
 "X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 STORM SEWER SCHEDULE -3
 FAI-72, MACARTHUR BLVD
 SECTION
 (84-9) RS-6; (G)Z
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. _____
 HORIZ. _____
 DATE: Mar-20-2008 08:24:46AM
 DRAWN BY: CLG
 CHECKED BY: JWM



© Copyright Hanson Professional Services Inc. 2008
 Mar-20-2008 08:24:46AM
 #FILES*
 LAYOUT: BLW 01/28/03
 DRAWN: CLG 01/28/03
 REVIEWED: BLW 01/28/03