

CODE NO.	DESCRIPTION	UNIT	TOTAL	INTERSECTION	SIGNALS	SIDEWALK
				100% STATE	95% STATE 5% CITY	50% STATE 50% CITY
				J000-1A	Y031-1F	SFTY-1B
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	13.0		13.0	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	13.0		13.0	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	402.0		402.0	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	430.0		430.0	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6.0		6.0	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4.0		4.0	
89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	2.0		2.0	
89502200	MODIFY EXISTING CONTROLLER	EACH	1.0		1.0	
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	45.0		45.0	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2.0		2.0	
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4.0		4.0	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	220.0	220.0		
44213200	SAW CUTS	FOOT	220.0	220.0		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	290.0			290.0
42400800	DETECTABLE WARNINGS	SQ FT	24.0			24.0
78300105	PAVEMENT MARKING REMOVAL	FOOT	60.0	60.0		
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	240.0	240.0		
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	60.0	60.0		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0		
67100100	MOBILIZATION	L SUM	1.0	1.0		
X0325974	EARTHWORK AND GRADING (SPECIAL)	L SUM	1.0	1.0		

* SPECIALTY ITEMS

FILE NAME =
C:\Projects\9603908\shsch.dgn

USER NAME = laughlinr1	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 1/1 IN.	CHECKED -	REVISED -
PLOT DATE = Apr-01-2008 07:08:17AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF SHEETS STA. TO STA.

F.A.P. RTE. 658	SECTION 102N	COUNTY SANGAMON	TOTAL SHEETS 7	SHEET NO. 3
CONTRACT NO. 72B77				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				