

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	9	2
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

\* - 72, 155  
 \*\* - D6 MEDIAN PROTECTION 2008  
 \*\*\* - LOGAN, MORGAN, PIKE & SCOTT COUNTIES

INDEX OF SHEETS:

1. COVER SHEET
2. GENERAL NOTES
3. SUMMARY OF QUANTITIES
- 4-5. SCHEDULES
- 6-9. DETAILS

LIST OF STANDARDS:

630001-07	635011-01
630301-04	701101-01
631011-04	701106-01
631031-06	701400-02
635006-02	701406-04
	701901

Route \_\_\_\_\_  
 Section \_\_\_\_\_  
 County \_\_\_\_\_

GENERAL NOTES:

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
2. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD NOTIFICATION BE NECESSARY, THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. A MINIMUM OF 48 HOURS PRIOR TO COMMENCING WORK - (800) 892-0123.
3. THE CONTRACTOR WILL BE REQUIRED TO CONTACT THE OPERATIONS ENGINEER (217) 782-7314 AT LEAST 72 HOURS PRIOR TO DRIVING ANY POSTS. TO MAKE SURE STATE OWNED UTILITIES ARE NOT IN THE WAY.
4. THE CONTRACTOR WILL BE REQUIRED TO REPAIR ANY AREAS OF TURF THAT ARE DAMAGED DURING THE EXECUTION OF THIS CONTRACT. THIS WORK WILL NOT BE MEASURED FOR PAYMENT AND WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
5. ALL GUARDRAIL SHALL HAVE A PRELIMINARY LAYOUT. GUARDRAIL POSTS SHALL BE ADJUSTED SO AS TO MISS ANY SHOULDER DRAINS, INLETS, PIPE CULVERTS, STORM SEWER OR ANY OTHER HAZARD THAT MAY INTERFERE WITH GUARDRAIL CONSTRUCTION.

EXAMINED	<u>FEB 27</u>	20 <u>08</u>
<u>W.R.J.</u>		
PROGRAM IMPLEMENTATION ENGINEER		
EXAMINED	<u>MARCH 13</u>	20 <u>08</u>
<u>W.R.J.</u>		
PROGRAM DEVELOPMENT ENGINEER		

DISTRICT SIX		
EXAMINED	<u>March 3</u>	20 <u>08</u>
<u>James A. Hooper</u>		
OPERATIONS ENGINEER		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

FAI 72 & FAI 155  
 SECTION D6 MEDIAN PROTECTION 2008  
 LOGAN, MORGAN, PIKE & SCOTT COUNTIES

Rev.