

PAVEMENT MARKING SCHEDULE

STATION	TYPE	URETHANE PAV'T MRKG
		LINE 5"
		WHITE
RT 172+200 TO 172+285.34	EDGE LINE	280 FT
RT 180+700 TO 181+926.82	EDGE LINE	4,025 FT
LT 172+200 TO 172+285.34	SKIP DASH	70 FT
LT 180+700 TO 181+926.82	SKIP DASH	1,010 FT
TOTALS		5,385 FT

NOTES:

STATIONS ARE APPROXIMATE.

MIXTURE REQUIREMENTS

THE FOLLOWING MIXTURE REQUIREMENTS
ARE APPLICABLE FOR THIS PROJECT

MIXTURE USE(S):	POLY H.M.A. S.C., MIX E, N50
AC/PG	SBS PG 70-22
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 105
MIXTURE COMP:	IL 9.5 OR 12.5
FRICTION AGG:	MIX "E"

PATCHING SCHEDULE

STATION	SIZE	STATION	SIZE
181+321	35 x 12	181+684	6 x 12
181+712	6 x 12	181+714	6 x 12

NOTE: ALL PATCHES ARE IN THE EAST
BOUND DRIVING LANE

SCHEDULES
FAI 72 (I-72)
SECTION D6 INTERMITTENT RS 2009-02
SANGAMON COUNTY