

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	025-0062 SFTY-2A		
50102400	CONCRETE REMOVAL	CU YD	15.1	15.1		
50104710	REMOVAL OF EXISTING BEARINGS	EACH	5	5		
50157300	PROTECTIVE SHIELD	SQ YD	145	145		
50300225	CONCRETE STRUCTURES	CU YD	13.4	13.4		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.9	2.9		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	31,250	31,250		
50501110	STRUCTURAL STEEL REMOVAL	POUND	30,690	30,690		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,530	2,530		
52100520	ANCHOR BOLTS, 1"	EACH	10	10		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1200	1200		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1200	1200		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	87.2	87.2		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	1		
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1		
67100100	MOBILIZATION	L SUM	1	1		