

RESURFACING SCHEDULE

LOCATION	HMA SURFACE REMOVAL 1.5 IN (SQ YD)	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	STRIP REFL CRACK CONT TREATMENT (FT)	LEVELING BINDER (MM) N70 .75 IN (TON)	HMA SURF CSE MIX "D" N70 1.5 IN (TON)
ST. LOUIS ROAD						
STA. 396+60 TO 399+20	1097.78	0.34	1.65		46.11	92.21
STA. 399+20 TO 410+58	4804.89	1.50	7.21		201.81	403.61
STA. 410+58 TO 416+66	2567.11	0.80	3.85		107.82	215.64
STA. 416+66 TO 418+53	810.33	0.25	1.22		34.03	68.07
STA. 418+53 TO 422+63	1822.22	0.57	2.73		76.53	164.55
STA. 422+63 TO 429+95	3253.33	1.02	4.88		136.64	293.78
STA. 429+95 TO 437+93	3546.67	1.11	5.32	3192	148.96	320.26
STA. 437+93 TO 440+35	1075.56	0.34	1.61	968	45.17	97.12
STA. 440+35 TO 448+18	3480.00	1.09	5.22	3132	146.16	314.24
STA. 448+18 TO 451+19	1337.78	0.42	2.01		56.19	119.40
STA. 451+19 TO 454+60	1799.56	0.56	2.70		75.58	136.85
CASEYVILLE ROAD						
	744.44	0.23	1.12		31.27	62.53
TOTALS	26,340	8	40	7,292	1,106	2,288

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

LOCATION	SOLID WHITE 4" (FT)		SKIP-DASH YELLOW 4" (FT)		SOLID YELLOW 4" (FT)		DOUBLE YELLOW 4" (FT)		SOLID WHITE 6" (FT)	SOLID WHITE 8" (FT)	DIAGONAL WHITE 12" (FT)	SOLID WHITE 12" (FT)	DIAGONAL YELLOW 12" (FT)	SOLID WHITE LETTERS & SYMBOLS (SQ FT)		RAISED REFLECTIVE PAVEMENT MARKERS (EACH)		
	EDGELINES	MEDIAN	LANE LINE	CENTERLINE	BI-DIRECTIONAL LANE	BI-DIRECTIONAL LANE	NPZ RT	MEDIAN	LANE LINE	CROSSWALK		STOP BAR	MEDIAN	BI-DIRECTIONAL TURN ARROWS	LEFT TURN ARROW	ONE-WAY	TWO-WAY	
ST. LOUIS ROAD																		
STA. 396+60 TO 403+69	1016				355	1418									94		36	
STA. 403+69 TO 410+58	1170				345	1378				72	54			94		34		
STA. 410+58 TO 417+18	1202				330	1320								62		34		
STA. 417+18 TO 422+63	926				273	1090				80	63			94		28		
STA. 422+63 TO 428+16	725				277	1106								62		28		
STA. 428+16 TO 429+96								720					65			10		
STA. 429+96 TO 437+93				199												10		
STA. 437+93 TO 445+21				182												9		
STA. 445+21 TO 449+00				95												5		
STA. 449+00 TO 451+20																3		
STA. 451+20 TO 453+16								784					85			10		
STA. 453+16 TO 454+17			101									13			31	3		
STA. 454+17 TO 454+60			25							139		14				1		
CASEYVILLE ROAD																		
	322	155		30									41					
SUBTOTALS	5361	155	126	506	1578	6312	379	1504	738	139	152	117	68	150	406	31	24	190
TOTALS					16659					139	152		335		436		213	