

TO BE SUPPLIED BY CONTRACTOR:

①

②

③

④

ON TYPE 3 BARRICADES -
2 MINIMUM AT EACH LOCATION

DETOUR NOTES

1. DETOUR SIGNS REQUIRED WILL BE SUPPLIED TO THE CONTRACTOR BY IDOT.
2. THE CONTRACTOR SHALL FURNISH THE POSTS AND ERECT SIGNS OR SKID MOUNTED SIGNS AT THE LOCATIONS SHOWN ON THE DETOUR SHEETS, AS DIRECTED BY THE R.E./R.T.. THE POSTS/SKIDS SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.
3. THE CONTRACTOR SHALL GIVE ILLINOIS DEPARTMENT OF TRANSPORTATION, BUREAU OF OPERATIONS TWO WEEKS NOTICE FOR SIGNS. THE CONTRACTOR SHALL PICK UP THE SIGNS AT THE T.M. BUILDING IN FAIRVIEW HGHTS, AND RETURN THEM UPON COMPLETION OF THE CONTRACT. CONTACT JEAN SLAPE 346-3289.
4. THE ABOVE NOTED WORK SHALL BE PAID FOR BY THE CONTRACT UNIT PRICE, LUMP SUM, FOR DETOUR SIGNING AND NO OTHER COMPENSATION WILL BE ALLOWED.
5. SIGN SPACING WILL BE 500' TO FIT FIELD CONDITIONS.
6. THE HEIGHT TO THE BOTTOM OF THE LOWEST SIGN SHALL NOT BE LESS THAN 6'.
7. CONTRACTOR SHALL FURNISH ADVANCE WARNING SIGNS, ROAD CLOSURE SIGNS, MESSAGE BOARDS AND TYPE 3 BARRICADES.
8. ALL ADVACNE WARNING SIGNS SHALL BE 48" FLOURESCENT ORANGE WITH FLASHING LIGHTS.

TO BE SUPPLIED BY IDOT:

④

⑤

⑥

⑦

⑪

⑫

⑬

⑮