

ILLINOIS DEPARTMENT OF TRANSPORTATION			URBAN TOTAL	ACHSIP	ACM	ACHSIP	ACHSIP					
SUMMARY OF QUANTITIES				QUANTITIES	1000-1A	1000-1A	Y031-1F	Y031-1F				
					ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS				
CODE NO	ITEM	UNIT			90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE				
20200100	EARTH EXCAVATION	CU YD	1190	1052	138							
20400800	FURNISHED EXCAVATION	CU YD	588	588								
20800150	TRENCH BACKFILL	CU YD	105	105								
25000210	SEEDING, CLASS 2A	ACRE	1.2	0.6	0.6							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108	54	54							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108	54	54							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108	54	54							
25100115	MULCH, METHOD 2	ACRE	1.2	0.6	0.6							
25100630	EROSION CONTROL BLANKET	SQ YD	1566	1566								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120	60	60							
28000300	TEMPORARY DITCH CHECKS	EACH	5	5								
28000400	PERIMETER EROSION BARRIER	FOOT	3710	3710								
28000500	INLET AND PIPE PROTECTION	EACH	22	22								
28100103	STONE RIPRAP, CLASS A2	SQ YD	40	40								
28200200	FILTER FABRIC	SQ YD	40	40								
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	5131	4446	685							
30201500	LIME	TON	99	86	13							
35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	3923	3238	685							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.3	3.1	0.2							
40600300	AGGREGATE (PRIME COAT)	TON	16	15	1							
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1324	1209	115							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	196	196								
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	53	53								
40600990	TEMPORARY RAMP	SQ YD	249	246								
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	876	818	58							
44000100	PAVEMENT REMOVAL	SQ YD	393	393								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	61	61								
44003100	MEDIAN REMOVAL	SQ FT	5840	5840								
44004250	PAVED SHOULDER REMOVAL	SQ YD	3459	3459								
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	22	22								
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	33	33								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	160	160								
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2236	2236								
50105220	PIPE CULVERT REMOVAL	FOOT	87	87								