

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
				I000	Y025		
CODE NO	ITEM	UNIT		100% STATE	50% STATE 50% RED BUD	50% STATE 50% BALDWIN	50% STATE 50% SPARTA
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	298	298			
28101200	DUMPED RIPRAP	TON	18	18			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	740	740			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	165.8	164.2	0.7	0.2	0.7
40600300	AGGREGATE (PRIME COAT)	TON	795	786	4	1	4
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	10861	10852			9
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5302	5302			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1704	1704			
40600990	TEMPORARY RAMP	SQ YD	324	324			
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	24190	23803	186	34	167
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	425	425			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	591	591			
44000100	PAVEMENT REMOVAL	SQ YD	425	425			
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	40426	15955	22078	400	1993
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	643	643			
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	2206	2101			105
44004250	PAVED SHOULDER REMOVAL	SQ YD	1081	1081			
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	1102	1102			
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	266	266			
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	997	997			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	175186	175186			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4252	4252			
48203039	HOT-MIX ASPHALT SHOULDERS, 10 1/2"	SQ YD	1441	1441			
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2223	2223			
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	100	100			
*63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4	4			
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	16	16			
63200310	GUARDRAIL REMOVAL	FOOT	1555	1555			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16			
67100100	MOBILIZATION	L SUM	1	1			

\*SPECIALTY ITEMS

FILE NAME = c:\proj\p01508\p10m\p101508a.dgn	USER NAME = dinstelmarjn	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 329	SECTION (125,126)RS-2	COUNTY RANDOLPH	TOTAL SHEETS 34	SHEET NO. 3
PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISIED - ---	SCALE: _____	SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/21/2008	DATE - ---	REVISIED - ---	CONTRACT NO. 76B38							