

# SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES |   |        | CONSTRUCTION TYPE CODE |                               |                             |       |
|-----------------------|---|--------|------------------------|-------------------------------|-----------------------------|-------|
| CODE NO               | ITEM  | UNIT   | TOTAL QUANTITIES       | 100% STATE ST. CLAIR CO. 1000 | 100% STATE CLINTON CO. 1000 | ----- |
| 40800020              | BITUMINOUS MATERIALS (PRIME COAT)               | TON    | 1.2                    | 1.2                           |                             |       |
| 40800030              | AGGREGATE (PRIME COAT)                          | TON    | 5.8                    | 5.7                           | 0.1                         |       |
| 44200629              | CLASS A PATCHES, TYPE I, 15 INCH                | SQ YD  | 5                      | 5                             |                             |       |
| 44200630              | CLASS A PATCHES, TYPE II, 15 INCH               | SQ YD  | 15                     | 15                            |                             |       |
| 44200631              | CLASS A PATCHES, TYPE III, 15 INCH              | SQ YD  | 62                     | 62                            |                             |       |
| 44200632              | CLASS A PATCHES, TYPE IV, 15 INCH               | SQ YD  | 80                     | 80                            |                             |       |
| 44201027              | CLASS B PATCHES, TYPE I, 15 INCH                | SQ YD  | 5                      | 5                             |                             |       |
| 44201031              | CLASS B PATCHES, TYPE II, 15 INCH               | SQ YD  | 67                     | 67                            |                             |       |
| 44201035              | CLASS B PATCHES, TYPE III, 15 INCH              | SQ YD  | 25                     | 25                            |                             |       |
| 44201037              | CLASS B PATCHES, TYPE IV, 15 INCH               | SQ YD  | 30                     | 30                            |                             |       |
| 44213000              | PATCHING REINFORCEMENT                          | SQ YD  | 162                    | 162                           |                             |       |
| 44213100              | PAVEMENT FABRIC                                 | SQ YD  | 55                     | 55                            |                             |       |
| 44213200              | SAW CUTS  | FOOT   | 1448                   | 1448                          |                             |       |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                 | CAL MO | 3                      | 3                             |                             |       |
| 67100100              | MOBILIZATION                                    | L SUM  | 1                      | 1                             |                             |       |
| 70100420              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 | EACH   | 8                      | 8                             |                             |       |
| 70100800              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 | L SUM  | 1                      | 1                             |                             |       |
| 70101805              | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)       | EACH   | 8                      | 8                             |                             |       |
| 70106800              | CHANGEABLE MESSAGE SIGN                         | CAL MO | 4                      | 4                             |                             |       |
| 70300100              | SHORT-TERM PAVEMENT MARKING                     | FOOT   | 600                    | 600                           |                             |       |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL              | SQ FT  | 200                    | 167                           | 33                          |       |
| *76001110             | PAINT PAVEMENT MARKING - LINE 4"                | FOOT   | 4743                   | 4743                          |                             |       |
| X4421000              | PARTIAL DEPTH PATCHING                          | TON    | 543                    | 556                           | ?                           |       |
| X4422027              | PARTIAL DEPTH REMOVAL 2.5                       | SQ YD  | 3875                   | 3828                          | 47                          |       |
| Z0016200              | DECK SLAB REPAIR (PARTIAL)                      | SQ YD  | 27.5                   | 27.5                          |                             |       |
| Z0017202              | DOWEL BARS 1 1/2"                               | EACH   | 248                    | 248                           |                             |       |
| Z0075310              | TIE BARS 3/4"                                   | EACH   | 194                    | 194                           |                             |       |

\* SPECIALTY ITEMS

|  |                    |               |              |   |                           |                                |
|--|--------------------|---------------|--------------|---|---------------------------|--------------------------------|
| FILE NAME: c:\projects\ad02408\plan\p1n2408p.dgn | USER NAME: a1fa-0b | DESIGNED: --- | REVISED: --- | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES     | * ST. CLAIR & CLINTON COUNTIES |
| PLT SCALE: 1/8" = 1'-0"                          | CHECKED: ---       | DATE: ---     | REVISED: --- | SCALE: -----                                      | SHEET NO. -- OF -- SHEETS | STA. ----- TO STA. -----       |
| PLT DATE: 4/18/2009                              |                    |               |              |   |                           |                                |

| A. RTE.                                       | SECTION    | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|------------|--------|--------------|-----------|
| 1-64  | 82:08.910H | -----  | 11           | 3         |
| CONTRACT NO. 76B46                            |            |        |              |           |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT |            |        |              |           |