

GENERAL NOTES

1. PRIOR TO EXCAVATING AND/OR TRENCHING THE CONTRACTOR SHALL LOCATE ALL EXISTING DEPARTMENT OWNED UNDERGROUND FACILITIES INCLUDING ELECTRICAL CABLES AND WELL DISCHARGE PIPES. ANY DAMAGE TO THE FACILITIES BY THE CONTRACTOR'S OPERATIONS SHALL BE IMMEDIATELY REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER AT THE CONTRACTOR'S EXPENSE. A PAY ITEM HAS BEEN INCLUDED TO LOCATE UNDERGROUND CABLE, IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO LOCATE THE DISCHARGE LINE.
2. COORDINATION WITH THE DEPARTMENT'S BUREAU OF OPERATIONS IS REQUIRED BEFORE ANY TRENCHING SHALL BE DONE TO LOCATE HIGHWAY LIGHTING / PUMP STATION / INTELLIGENT TRANSPORTATION SYSTEM FACILITIES AND TO COORDINATE OTHER FIELD ACTIVITIES. THE CONTRACTOR SHALL CONTACT (IDOT) PETE SAWYER AT (618) 304-2082 BEFORE COMMENCING WORK.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- AMEREN IP - GAS & ELECTRIC
- AT&T ILLINOIS - COMMUNICATIONS
- CENTER POINT ENERGY - GAS TRANSMISSION
- CHARTER COMMUNICATIONS, INC. - CABLE TV
- CITY OF VENICE - SANITARY SEWER
- CONSOLIDATED COMMUNICATION- COMMUNICATIONS
- ILLINOIS AMERICAN WATER CO. - WATER
- LEVEL 3 COMMUNICATIONS, LLC - COMMUNICATIONS
- QWEST COMMUNICATIONS- COMMUNICATIONS
- SPRINT/NEXTEL COMMUNICATIONS CO. - COMMUNICATIONS
- VERIZON BUSINESS - COMMUNIATIONS
- 360 NETWORKS (USA) INC. - COMMUNICATIONS

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON- J.U.L.I.E. MEMBERS MUST BE NOTIFIED DIRECTLY.)

4. ALL 7 PUMPS SHALL BE AVAILABLE FOR USE DURING HIGH WATER. THE ENGINEER WILL DETERMINE NUMBER OF PUMPS REQUIRED TO DEWATER. A TYPICAL DATE FOR LOW WATER IS JULY, 1, HOWEVER, THE CONTRACTOR SHALL TAKE INTO ACCOUNT THE UNPREDICTABILITY OF THE WEATHER, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. THE ENGINEER WILL DETERMINE WHEN LOW WATER HAS BEEN OBTAINED.
5. A MINIMUM OF 4 PUMPS SHALL BE AVAILABLE FOR USE AT ALL TIMES. THE ENGINEER WILL DETERMINE THE NUMBER OF PUMPS REQUIRED TO DEWATER. SEE SPECIAL PROVISION MINIMUM DEWATERING REQUIREMENTS.
6. THE EXISTING PUMPS AND MOTORS SHALL BE SALVAGED AND WILL BECOME THE PROPERTY OF THE STATE. THE CONTRACTOR SHALL DELIVER THEM TO THE VENICE PUMP STATION. REMOVAL OF THE EXISTING PUMPS/MOTORS SHALL BE INCLUDED IN THE PAY ITEM SUBMERSIBLE TURBINE PUMP TYPE 1.
7. ALL MANHOLE LIDS AND RISERS SHALL REMAIN THE PROPERTY OF THE STATE. THE CONTRACTOR SHALL DELIVER THESE TO THE TRAFFIC MAINTENANCE BUILDING AT 9601 ST. CLAIR AVE., FAIRVIEW HEIGHTS. PLEASE CONTACT PETE SAWYER FOR A TIME AND DATE (618-304-2082).
8. TRAFFIC CONTROL STANDARD 701601 IS TO BE USED TO TRENCH NEW CONDUIT TO PUMPS 3, 4, 5, AND 6A, DUE TO THE LIMITED AREA BETWEEN THE RAILROAD ABUTMENT AND EDGE OF PAVEMENT. THIS PAY ITEM WILL BE DEDUCTED FROM THE CONTRACT IF NOT NEEDED.
9. RAILROAD FLAGMEN WILL BE REQUIRED AND SHALL BE PAID FOR IN ACCORDANCE WITH ARTICLE 107.12.
10. B.M. AT RAILROAD SPIKE IN P.P. EAST OF PUMP STATION ELEV. 411.36.
11. THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS THAT ARE ON THE PLANS PRIOR TO ORDERING ANY MATERIAL.

COMMITMENTS

THE CONTRACTOR SHALL REMOVE AND DISPOSE REGULATED SUBSTANCES UNDER THE OTHER PROVISIONS OF THIS CONTRACT. SEE SPECIAL PROVISION "NON-SPECIAL WASTE WORKING CONDITION" FOR THE LIMITS OF NON-SPECIAL WASTE LOCATIONS.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND COMMITMENTS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILEL#		DRAWN -	REVISED -			788	27T-7	MADISON	9	2	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			CONTRACT NO. 76B51					
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE:	SHEET NO. 2 OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.