

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	Y007 STATE-100%		
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25		
25100105	MULCH, METHOD 1	ACRE	0.25	0.25		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50		
60266500	VALVE VAULTS TO BE REMOVED	EACH	7	7		
*66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	54	54		
*66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
*66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
80300100	LOCATING UNDERGROUND CABLE	FOOT	1000	1000		
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	250	250		
81306200	DRILL EXISTING JUNCTION BOX	EACH	7	7		
81603075	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	770	770		
81603115	UNIT DUCT, 600V, 3-1C NO.1, 1/C NO.1 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	3015	3015		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1050	1050		
X0320903	CIRCUIT BREAKER AND ENCLOSURE	EACH	7	7		
X0322618	SUBMERSIBLE TURBINE PUMP TYPE 1	EACH	7	7		
X0322628	FILL EXISTING PIEZOMETER	EACH	7	7		
X0322629	WELL ENCLOSURE BOX	EACH	7	7		
X0322631	WELL HEAD EXTENSION	EACH	7	7		
XX001290	CONCRETE BOLLARDS	EACH	42	42		
Z0040000	PIEZOMETERS	EACH	7	7		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 788	SECTION 27T-7	COUNTY MADISON	TOTAL SHEETS 9	SHEET NO. 3		
#FILE#		DRAWN -	REVISED -					CONTRACT NO. 76B51						
		CHECKED -	REVISED -											
		DATE -	REVISED -											
							SCALE: 1/50		SHEET NO. 3 OF		SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	