

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL	CONSTRUCTION TYPE CODE					TMC D8 OFFICE
CODE NO	ITEM	UNIT	QUANTITIES	MP025528.4 STA. 1493+05	MP025529.3 STA. 1531+50	MP025530.9 STA. 1619+00	MP027008.4 STA. 528+21	F.O. BACKBONE CONDUIT, & HANDHOLES	
89502215	MODIFY EXISTING CONTROLLER FOUNDATION	EACH	1			1			
X0322227	CLOSED CIRCUIT TELEVISION CAMERA SYSTEM	EACH	1		1				
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	20342					20342	
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	4		1		1	2	
X0325066	2955 LAYER 2 SWITCH	EACH	1				1		
X0325073	MODIFY EXISTING CONTROLLER CABINET TYPE B	EACH	2	1		1			
X0325075	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., FIBERGLASS BULLET RESISTANT	FOOT	183					183	
X0325076	WIDE AREA NETWORK	L SUM	1	0.1	0.1	0.1	0.1		0.6
X0325851	FIBER OPTIC UTILITY MARKER(SUPPLIED BY OTHERS) IDENTIFICATION AND INSTALLATION	EACH	70					70	
X0326092	RELOCATE SURVEILLANCE CAMERA SYSTEM CLOSED CIRCUIT TELEVISION	EACH	1			1			
X0325456	3750-12S LAYER 3 SWITCH	EACH	2			1			1
X0325460	CONTROLLER CABINET TYPE III, SPECIAL (AIR-CONDITIONED)	EACH	2		1	1			
X0325461	GLC-T SFP MODULE	EACH	1			1			
X0325473	MODIFY EXISTING CONTROLLER CABINET TYPE C	EACH	2	1		1			
X0325475	MODIFY EXISTING CONTROLLER CABINET TYPE E	EACH	2	1		1			
X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	1		1				
X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	1			1			
X0325483	SFP-GE-L SFP MODULE	EACH	7		2	5			
X0325487	WIRED COMMUNICATION DATA CONVERTOR	EACH	4		1	2	1		
X0325523	500G LAYER 2 SWITCH	EACH	1			1			
X0325525	GLC-FE-100 LX SFP MODULE	EACH	1			1			
X0325575	CONDUIT PUSHED, 4" DIA., PVC, SCHEDULE 40	FOOT	751					751	
X0325576	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC, SCHEDULE 40	FOOT	731					731	
X0326112	3560-24PS LAYER 3 SWITCH	EACH	1		1				
X2010510	CLEARING AND GRUBBING	L SUM	1					1	
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	18546					18546	
X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S. M. F. O.	FOOT	21649					21649	
XX003581	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 1/C	FOOT	2222		2222				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1					1	

PLOT DATE = 3/17/2008
 FILE NAME = c:\projects\2008\electrical\11\sp1n02608a.dgn
 PLOT SCALE = 50.0000 / IN.
 REFERENCE = 8950

FILE NAME =	USER NAME = prestonme	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\projects\2008\electrical\11\sp1n02608a.dgn		DRAWN -	REVISED -		SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____				•	DIST 8 ITS 2009-1	MADISON	28	4
	PLOT SCALE = 50.0000 / IN.	CHECKED -	REVISED -						•255/270				
	PLOT DATE = 3/17/2008	DATE -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				