



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2008

SUBJECT: FAP Route 582 (IL 111)  
Project ACF-0582 (030)  
Section (6-1, 6-2)RS-2  
Madison County  
Contract No. 76B63  
Item No. 339, June 13, 2008 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 and 2 of the Schedule of Prices.
2. Revised sheets 5 and 6 of the Fold-Up Plans.
3. Replaced sheet 14 of the Fold-Up Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by 'P.E.' in smaller letters.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76B63

State Job # - C-98-029-08  
 PPS NBR - 8-70076-0000  
 County Name - MADISON - -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - (6-1,6-2)RS-2

Project Number  
ACF-0582/030/

Route  
FAP 582

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
Z0048665	RR PROT LIABILITY INS	L SUM	1.000					
Z0076600	TRAINEES	HOUR	500.000		0.800		400.000	
* 40600200	BIT MATLS PR CT	TON	33.000					
* 40600300	AGG PR CT	TON	163.000					
* 40600645	LEV BIND MM N90	TON	3,594.000					
40600895	CONSTRUC TEST STRIP	EACH	1.000					
40600982	HMA SURF REM BUTT JT	SQ YD	1,555.000					
40600990	TEMPORARY RAMP	SQ YD	233.000					
* 40603545	P HMA SC "D" N90	TON	7,189.000					
40800020	BIT MATLS PR CT	TON	0.400					
40800030	AGG PR CT	TON	1.900					
40800050	INCIDENTAL HMA SURF	TON	107.000					
44000152	HMA SURF REM 3/4	SQ YD	64,164.000					
44000158	HMA SURF REM 2 1/4	SQ YD	40,158.000					
44200164	PAVT PATCH T1 14	SQ YD	12.000					
			* REVISED : MAY 27, 2008					

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76B63

State Job # - C-98-029-08  
 PPS NBR - 8-70076-0000  
 County Name - MADISON - -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - (6-1,6-2)RS-2

Project Number  
 ACF-0582/030/

Route  
 FAP 582

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44200168	PAVT PATCH T2 14	SQ YD	290.000				
44200172	PAVT PATCH T3 14	SQ YD	224.000				
44200174	PAVT PATCH T4 14	SQ YD	1,437.000				
44300200	STRIP REF CR CON TR	FOOT	47,520.000				
48102100	AGG WEDGE SHLD TYPE B	TON	1,394.000				
* 48203100	HMA SHOULDERS	TON	1,574.000				
63000000	SPBGR TY A	FOOT	962.500				
63100045	TRAF BAR TERM T2	EACH	3.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	7.000				
63200310	GUARDRAIL REMOV	FOOT	1,387.500				
67000400	ENGR FIELD OFFICE A	CAL MO	3.000				
67100100	MOBILIZATION	L SUM	1.000				
70100310	TRAF CONT-PROT 701421	L SUM	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
			* REVISED : MAY 27, 2008				

# SUMMARY OF QUANTITIES

TOTAL SHEETS	SHEET NO.
28	5
CONTRACT NO.: 76B63	

CODE NO	ITEM	UNIT	URBAN 80% FED./20% STATE 1000 TOTAL QUANTITIES	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33	△
40600300	AGGREGATE (PRIME COAT)	TON	163	△
40600895	CONSTRUCTING TEST STRIP	EACH	1	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	3594	△
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1555	
40600990	TEMPORARY RAMP	SQ YD	233	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	7189	△
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	
40800030	AGGREGATE (PRIME COAT)	TON	1.9	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	107	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	64164	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	40158	
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	12	
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	290	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	224	
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	1437	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	47520	

## SUMMARY OF QUANTITIES

FAP 582 (IL 111)  
SECTION (6-1,6-2)RS-2  
MADISON COUNTY


\*\*DATE\*\*  
 \*DATE-TIME\*  
 \*JOB-SPEC\*

Rev. PLOT DATE: \*DATE-TIME\*

△ Rev. 5-27-08

# SUMMARY OF QUANTITIES

TOTAL SHEETS	SHEET NO.
28	6
CONTRACT NO. 76B63	

CODE NO	ITEM	UNIT	QUANTITIES
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1394
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1574 
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	962.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7
63200310	GUARDRAIL REMOVAL	FOOT	1387.5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11796


URBAN  
60% FED / 20% STATE  
TOTAL

## SUMMARY OF QUANTITIES

FAP 582 (IL 111)  
SECTION (6-1,6-2)RS-2  
MADISON COUNTY

\*SPECIALTY ITEMS

PLOT DATE: \_DATE-TIME\_

 Rev. 5-27-

\*\*DATE\*\*  
\*DATE-TIME\*  
\*DGN-SPEC\*

LOCATION	MI STA	Main Lin (SY)	Shoulder (SY)	LEVELING BINDER (MM), N90 (TONS)	POLY. HMA SURFACE COURSE, MIX "D", N90 (TONS)	BIT. MATL'S (PRIME COAT) (TONS)	AGGREGATE (PRIME COAT) (TONS)	HMA SHOULDERS (TONS)
0	0.4	13510.9	6570.6	567.5	1134.9	6.3	31.4	551.9
BRIDGE LOCATION 2								
0.4	0.6	3050.6	1173.4	128.1	256.3	1.3	6.6	98.6
0.6	1.2	6834.7	2702.3	287.1	574.1	3.0	14.9	227.0
BRIDGE LOCATION 1								
1.2	2.1	16778.7		704.7	1409.4	5.3	26.3	
2.1	2.5	5990.8		251.6	503.2	1.9	9.4	
2.5	3.4	16736.6	1840	702.9	1405.9	5.8	29.1	154.6
3.4	4.1	14709.4	5366.6	617.8	1235.6	6.3	31.4	450.8
4.1	4.5	7967.7	1088.8	334.6	669.3	2.8	14.2	91.5
		85579.4	18741.7	3594	7189	33	163	1574

### HMA Surface Removal

MI Sta	2 1/4" (SY)	.75" (SY)
0.0-0.4	20082	
0.4-0.5		4224
0.6-1.0		9537
1.0-2.2		16779
2.2-2.5		5991
2.5-3.6		18577
3.6-4.1	20076	
4.1-4.5		9057
	40158	64164

\*DATE\*  
\*DATE-TIME\*  
\*DRAW-SPEC\*

PLOT DATE: \*DATE-TIME\*

SCHEDULE  
OF QUANTITIES  
FAP 582 (IL 111)  
SECTION (6-1,6-2)RS-2  
MADISON COUNTY

Rev. Sheet 5-27-08