

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	22	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

FAP 322 (US 51) PAVEMENT MARKING SCHEDULE
LOCATION 2

- FAS 1909 & FAP 322
- D9 PAVEMENT PRESERVATION FY08
- JACKSON AND UNION COUNTIES

STATION TO STATION	PAINT PAVEMENT MARKING					THPL PAV'T MARKING	TEMPORARY				NOTES						
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH YELLOW	12 INCH WHITE	24 INCH WHITE	LETTERS & SYMBOLS	4 INCH	12 INCH	24 INCH	LETTERS & SYMBOLS							
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT							
US 51- STA. 238+50 TO STA. 378+65																	
LT & RT	238+50.0				240+04.2		308					347			EDGE LINE		
EQ STA 240+04.17 (BK.) = STA. 3040+04.17 (AH.)																	
	3040+04.2				3051+50.0							286					
LT & RT	3040+04.2				3073+50.0		6692					6,692			EDGE LINE		
	3058+28.0				3073+50.0							381					
OMIT SN 091-0071 STA. 3073+50 TO STA. 3075+71																	
	3075+71.0				3097+65.0							549					
LT & RT	3075+71.0				3101+03.2		5064					5064			EDGE LINE		
	3098+84.0				3101+03.2							55					
EQ STA 3101+03.20 (BK.) = STA. 304+62.66 (AH.)																	
	304+62.7				331+78.0							679					
LT	304+62.7				374+80.0		7017					7,017					
RT	304+62.7				374+13.0		6,950					6,950			EDGE LINE		
	344+67.0				367+07.0							560					
LT	375+63.0				378+65.0		302					302					
RT	376+44.3				378+65.0		221					221			EDGE LINE		
	3051+50.0				3069+31.0							1,781			NO PASSING ZONE		
LT	3097+65.0				313+29.0							1,205			NO PASSING ZONE		
LT	331+78.0				344+85.0							1,307			NO PASSING ZONE		
LT	365+98.0				366+98.0							100			NO PASSING ZONE		
LT	366+98.0				373+78.0							1,360			NO PASSING ZONE		
LT	373+78.0				374+78.0							200			NO PASSING ZONE		
LT	375+73.0				376+73.0		100.0					100			LEFT TURN LANE		
	3041+83.0				3058+28.0							1,645			NO PASSING ZONE		
RT	3087+30.0				3098+84.0							1,154			NO PASSING ZONE		
RT	321+09.0				334+67.0							1,358			NO PASSING ZONE		
RT	365+98.0				366+98.0							100					
RT	366+98.0				373+78.0							1,360					
RT	366+98.0				373+78.0							310.0			NO PASSING ZONE		
RT	373+78.0				374+78.0		100.0					100			LEFT TURN LANE		
RT	375+73.0				376+73.0							200			NO PASSING ZONE		
RT	376+73.0				378+65.0							768			NO PASSING ZONE		
RT	373+88.0											20.8			"ONLY"		
RT	374+16.0											15.6			LT TURN ARROW		
LT	376+27.0											15.6			LT TURN ARROW		
LT	376+55.0											20.8			"ONLY"		
SUB-TOTALS							26,754	12,538.0	2,549.0	439.0	0.0	72.8	41,841	439.0	72.8		
TOTALS AT US 51 LOCATION 2								41,841		439	0	72.8	41,841	439	0	72.8	

FAP 322 (US 51) PAVEMENT MARKING SCHEDULE
TOTALS FOR LOCATION 1 AND LOCATION 2

	PAINT PVT MRK - LINE 4"	PAINT PVT MRK - LINE 12"	PAINT PVT MRK - LINE 24"	THPL PVT MRK - LTR & SYM	TEMP PVT MRK - LINE 4"	TEMP PVT MRK - LINE 12"	TEMP PVT MRK - LINE 24"	TEMP PVT MRK - LTR & SYM
	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT
TOTALS AT US 51 LOCATIONS 1 & 2	121,224.0	1,133.0	66.0	254.8	121,224.0	1,133.0	66.0	254.8

PLOT DATE = 10/27/2007
 FILE NAME = I:\PROJECTS\78017\msoadgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = msoadgn