

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, AND MIXTURE REQUIREMENTS
3 - 4	SUMMARY OF QUANTITIES
5 - 6	TYPICAL SECTIONS
7 - 12	SCHEDULES OF QUANTITIES
13 - 17	PLAN SHEETS
18 - 21	RIPRAP AND EROSION CONTROL PLAN SHEETS
22 - 23	TRAFFIC CONTROL PLAN S.N. 083-0009 AND S.N. 083-0010
24	DETAIL: SHOULDER RUMBLE STRIPS
25	DETAILS: STEEL BRIDGE RAIL
26 - 27	DETAILS: PRECAST CONCRETE BOX CULVERTS AND END SECTIONS
28 - 29	DETAILS: CAST-IN-PLACE BOX CULVERT HEADWALLS
30 - 64	CROSS SECTIONS HIGHWAY STANDARDS

MIXTURE REQUIREMENTS

LOCATION(S):	HOT-MIX ASPHALT SHOULDERS
MIXTURE USE(S):	HOT-MIX ASPHALT SHOULDERS
AC/PG:	PG58-22
RAP % (MAX):	50
DESIGN AIR VOIDS:	2.0 %, 30 GYRATION DESIGN
MIXTURE COMPOSITION: (GRADATION MIXTURE)	HMA SHOULDERS
FRICTION AGGREGATE:	NONE

GENERAL NOTES

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:

ALL AGGREGATE	RIPRAP
2.05 TONS/CU. YD.	1.50 TONS/CU. YD.

THE QUANTITIES SHOWN IN THE PLANS FOR EROSION CONTROL ITEMS ARE ESTIMATES. THE ACTUAL AMOUNTS USED AND LOCATIONS SHALL BE DETERMINED BY THE ENGINEER.

A QUANTITY OF PAINT PAVEMENT MARKING - LINE 4" HAS BEEN INCLUDED IN THE PLANS. THIS SHALL BE USED RESTRIPE THE EDGELINES WITHIN THE PROJECT LIMITS THAT MAY BE COVERED WITH ASPHALT DURING HMA SHOULDER INSTALLATION, OR AS DIRECTED BY THE ENGINEER.

COMMITMENTS

NONE

HIGHWAY STANDARDS

000001-05	635006-02
001001-01	635011-01
280001-04	701001-01
442201-03	701006-02
509001	701311-02
	701326-02
	<b>701901</b>
	704001-04
630001-07	
631011-04	
631032-03	
631033-02	BLR 21-7
631041-01	BLR 22-5

Prepared By: Joe J. Daniewicz  
DISTRICT STUDIES & PLANS ENGINEER

Examined By: James Davis Emery  
DISTRICT LAND ACQUISITION ENGINEER

Examined By: Carrie Nelson  
DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By: Wesley H. Lamont  
DISTRICT OPERATIONS ENGINEER

Examined By: Joseph L. Linn  
DISTRICT CONSTRUCTION ENGINEER

Examined By: Bruce Seibles  
DISTRICT MATERIALS ENGINEER

Examined By: John Swathlow  
DISTRICT PROJECT IMPLEMENTATION ENGINEER

Examined By: Dan L. Clayton  
ASSISTANT REGIONAL ENGINEER

Approved By: Man C. Harris  
DEPUTY DIRECTOR OF HIGHWAYS, REGION 5 ENGINEER

DATE: March 14, 2008

FILE NAME =  
c:\projects\d901907\d901907ms.m32

USER NAME = thomashf  
PLOT SCALE = 50,0000" / IN.  
PLOT DATE = 3/14/2008

DESIGNED -	---	REVISED -	---
DRAWN -	---	REVISED -	---
CHECKED -	---	REVISED -	---
DATE -	---	REVISED -	---

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, GENERAL NOTES, STANDARDS & MIX REQUIREMENTS

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
881	D9 SAFETY FY08-1	VARIOUS	64	2
CONTRACT NO. 78038			Rev.	

FED. ROAD DIST. NO. \_\_\_\_\_ ILLINOIS FED. AID PROJECT