

## SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	90% FEDERAL / 10% STATE				
			TOTAL QUANTITY	CONSTRUCTION TYPE CODE - SFTY - 2A		WILLIAMSON COUNTY	JOHNSON COUNTY
				SALINE COUNTY URBAN	SALINE COUNTY RURAL		
50900200	STEEL RAILING, TYPE 2399	FOOT	201		201		
50901705	TUBULAR THRIE BEAM RETROFIT RAIL FOR BRIDGES	FOOT	640		440		200
54001000	BOX CULVERT END SECTIONS	EACH	8	2	6		
54003000	CONCRETE BOX CULVERTS	CU YD	33		33		
54020402	PRECAST CONCRETE BOX CULVERT 4' X 2' (M273)	FOOT	34		34		
54020503	PRECAST CONCRETE BOX CULVERT 5' X 3' (M273)	FOOT	158	36	122		
54020504	PRECAST CONCRETE BOX CULVERT 5' X 4' (M273)	FOOT	64		64		
54020604	PRECAST CONCRETE BOX CULVERT 6' X 4' (M273)	FOOT	38		38		
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,775		1400		375
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		2		
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8		8		
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2		2		
63100101	TRAFFIC BARRIER TERMINAL, TYPE 9	EACH	8		4		4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	20	2	14		4
63200310	GUARDRAIL REMOVAL	FOOT	863	50	442		371
64200105	SHOULDER RUMBLE STRIP	FOOT	150,025	15705	94001	16647	23672
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	0.30	1.98	0.30	0.42
67100100	MOBILIZATION	L SUM	1	0.10	0.66	0.10	0.14
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.10	0.66	0.10	0.14
70101805	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	2		2		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	0.10	0.66	0.10	0.14
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	0.20	0.80		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	320		320		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	320		320		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	142,175	15705	85996	16887	23587
78200420	GUARDRAIL MARKERS, TYPE B	EACH	32		26		6
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	20	2	14		4

\* SPECIALTY ITEMS

FILE NAME c:\projects\901907\901907.soh.m32	USER NAME thumashp	DESIGNED ---	REVISED ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 881	SECTION D9 SAFETY FY08-1	COUNTY VARIOUS	TOTAL SHEETS 64	SHEET NO. 4
PLOT SCALE = 1/8" = 1' / IN. PLOT DATE = 3/15/2006				SCALE: NONE    SHEET NO. 2 OF 2 SHEETS    STA.    TO STA.		CONTRACT NO. 78038 FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				