

TRAFFIC BARRIER SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	HANDRAIL CONCRETE REM FOOT	STEEL BRIDGE RAIL FOOT	TUBULAR THRIE BEAM RAIL FOOT	TRAFFIC BARRIER TERMINAL					GUARDRAIL MARKERS EACH	TERMINAL MARKERS DIRECT APPLIED EACH	REMARKS
						TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 6A EACH	TYPE 6B EACH	TYPE 9 EACH			
SALINE COUNTY													
FEAZEL ROAD													
RT 76+90.00 TO 77+15.00	25.00					1						1	TERMINAL REPLACEMENT
LT 77+25.00 TO 77+50.00	25.00					1						1	TERMINAL REPLACEMENT
083 - 0009													
RT 379+15.00 TO 379+96.25		31.25				1					1	1	
RT 379+96.25 TO 380+40.00								1					
RT 380+40.00 TO 380+84.00			44.0	44.0									BRIDGE RAIL UPDATE
RT 380+84.00 TO 381+27.75								1					
RT 381+27.75 TO 382+40.25		62.50				1					1	1	
LT 379+00.00 TO 379+50.00						1							
LT 379+50.00 TO 379+70.00		31.25					1				1		
LT 380+46.00 TO 380+56.00							1	1					
LT 380+56.00 TO 381+00.00			44.0	44.0									BRIDGE RAIL UPDATE
LT 381+00.00 TO 381+43.75								1					
LT 381+43.75 TO 383+56.25		162.50				1					3	1	
083 - 0010													
RT 416+83.75 TO 418+96.25		162.50				1					3	1	
RT 418+96.25 TO 419+40.00								1					
RT 419+40.00 TO 420+00.00			60.0	60.0									BRIDGE RAIL UPDATE
RT 420+00.00 TO 420+43.75								1					
RT 420+43.75 TO 421+56.25		62.50				1					1	1	
LT 417+83.75 TO 418+96.25		62.50				1					1	1	
LT 418+96.25 TO 419+40.00								1					
LT 419+40.00 TO 420+00.00			60.0	60.0									BRIDGE RAIL UPDATE
LT 420+00.00 TO 420+43.75								1					
LT 420+43.75 TO 422+56.25		162.50				1					3	1	
083 - 0011													
RT 612+54.50 TO 613+04.50						1						1	TERMINAL REPLACEMENT
RT 613+04.50 TO 614+42.00	102.00	137.50									2		INSTALL WITH 1:40 FLARE
RT 614+42.00 TO 614+67.00	25.00									1			TERMINAL REPLACEMENT
RT 614+67.00 TO 614+95.00	25.00				25.0								THRIE BEAM RETROFIT
RT 614+95.00 TO 616+65.00					170.0								THRIE BEAM RETROFIT
RT 616+65.00 TO 616+92.00	25.00				25.0								THRIE BEAM RETROFIT
RT 616+92.00 TO 617+17.00	25.00									1			TERMINAL REPLACEMENT
RT 617+17.00 TO 618+04.50	26.00	87.50									2		INSTALL WITH 1:40 FLARE
RT 618+04.50 TO 618+54.50						1						1	TERMINAL REPLACEMENT
LT 613+04.50 TO 613+54.50						1						1	TERMINAL REPLACEMENT
LT 613+54.50 TO 614+42.00	26.00	87.50									2		INSTALL WITH 1:40 FLARE
LT 614+42.00 TO 614+67.00	25.00									1			TERMINAL REPLACEMENT
LT 614+67.00 TO 614+95.00	25.00				25.0								THRIE BEAM RETROFIT
LT 614+95.00 TO 616+65.00					170.0								THRIE BEAM RETROFIT
LT 616+65.00 TO 616+92.00	25.00				25.0								THRIE BEAM RETROFIT
LT 616+92.00 TO 617+17.00	25.00									1			TERMINAL REPLACEMENT
LT 617+17.00 TO 618+54.50	88.00	137.50									2		INSTALL WITH 1:40 FLARE
LT 618+54.50 TO 619+04.50						1						1	TERMINAL REPLACEMENT
083 - 9900													
RT 680+76.75 TO 681+26.75						1						1	
RT 681+26.75 TO 682+39.25		112.50									2		INSTALL WITH 1:40 FLARE
RT 682+39.25 TO 682+95.50													
LT 683+69.50 TO 684+25.75													
LT 684+25.75 TO 685+25.75		100.00									2		INSTALL WITH 1:40 FLARE
LT 685+25.75 TO 685+75.75						1						1	
SUBTOTALS:	492.0	1400.0	208	208	440.0	16	2	8	2	4	26	16	