

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE *	EMBANKMENT *	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) *
STATION TO STATION	CU YD	CU YD	CU YD	CU YD
LOCATION 1 53+40 TO 53+65	1	1	20	-19
LOCATION 2 160+75 TO 162+75	219	175	81	94
LOCATION 3 165+50 TO 166+75	62	50	16	34
LOCATION 4 234+00 TO 234+75	49	39	13	26
LOCATION 5 240+00 TO 241+50	102	82	14	68
LOCATION 6 665+50 TO 670+75	78	62	3	59
LOCATION 7 857+25 TO 869+50	117	94	4	90
TOTALS	628			

* FOR INFORMATION ONLY

A 20% SHRINKAGE FACTOR HAS BEEN APPLIED TO EARTH EXCAVATION AND BORROW EXCAVATION.
SEE SAFETY SHOULDER SCHEDULE FOR ADDITIONAL EARTH EXCAVATION QUANTITIES.

FILE NAME = c:\projects\901907\901907schm32	USER NAME = thomashf	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES - EARTHWORK	F.A.P. RTE. 881	SECTION D9 SAFETY FY08-1	COUNTY VARIOUS	TOTAL SHEETS 64	SHEET NO. 11
PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISIED - ---	REVISIED - ---	SCALE: NONE	SHEET NO. ___ OF ___ SHEETS	STA. _____	TO STA. _____	CONTRACT NO. 78038		
PLOT DATE = 3/18/2008	DATE - -----	REVISIED - ---	REVISIED - ---				FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT			