CONTRACT NO. 78039

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	29	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1-2)RS-3,(1-3)RS-2

SHOULDER RESURFACING SCHEDULE

LOCATION STATION TO STATION				HMA SHOULDER (TON)	AGG. SHOULDER, TYPE B (TON)	POLY BIT MATLS (PR CT) (GAL)	AGGREGATE (PR CT) (TON)	GRADING & SHAPING EX SHOULDERS (SQ YD)
FAP 331 - MAINLINE								
RURAL LIMITS								
Left	467+57.00	TO	492+98.89	226.0	32.2	152.5	2.54	
Left	493+70.00	TO	520+21.83	236.0	33.6	159.1	2.65	
Left	520+88.80	TO	559+96.29	347.0	49.5	234.4	3.91	
Left	560+70.30	TO	574+20.99	120.0	17.1	81	1.35	
Left	492+34.00	TO	492+93.00					80
RURAL SUBTOTALS				929.0	132.4	627	10.45	80
Left	574+20.99	TO	586+12.15	106.0	15.1	71.5	1.19	
Left	586+91.60	TO	615+01.50	250.0	35.6	168.6	2.81	
EQ. STA. 615+01.50 (BK.) = STA. 615+05.84 (AH)								
Left	615+05.84	TO	620+45.00	48.0	6.8	32.3	0.54	
URBAN SUBTOTALS				404.0	57.5	272.4	4.54	0
Right	467+57.00	TO	492+72.92	372.0	31.9	251.6	4.19	
Right	493+84.15	TO	519+85.01	385.0	33.0	260.1	4.33	
Right	521+77.86	TO	559+75.19	561.0	48.2	379.7	6.33	
Right	560+88.93	TO	574+20.99	197.0	16.9	133.2	2.22	
RURAL SUBTOTALS				1515.0	130.0	1024.6	17.1	0
Right	574+20.99	TO	585+80.15	171.0	14.7	115.9	1.93	
Right	587+06.07	TO	615+01.50	413.0	35.4	279.5	4.66	
Right	615+05.84	TO	620+45.00	80.0	6.8	53.9	1	
URBAN SUBTOTALS				664.0	56.9	449.3	7.6	0
SIDE ROADS								
MAIN ST.		SW QUAD.		12.0	1.1	8.3	0.14	
MAIN ST.		SE QUAD.		12.0	1.0	8.2	0.14	
WOLF CREEK RD.		SW QUAD.		24.0	2.0	15.9	0.26	
WOLF CREEK RD.		SE QUAD.		28.0	2.4	18.9	0.32	
SAMUEL RD.		SW QUAD.		13.0	1.1	8.5	0.14	
SAMUEL RD.		SE QUAD.		11.0	1.0	7.6	0.13	
RURAL SUBTOTALS				100.0	8.6	67.4	1.13	0
BRIGGS RD.		SW QUAD.		13.0	1.1	9.0	0.15	
BRIGGS RD.		SE QUAD.		13.0	1.1	8.6	0.14	
URBAN SUBTOTALS				26.0	2.2	17.6	0.29	
RURAL TOTALS				2544.0	271.0	1719.0	28.7	80
URBAN TOTALS				1094	116.6	739.3	12.4	0
PROJECT TOTALS				3,638	388	2458.3	41.1	80

PCC PAVEMENT SCHEDULE

LOCATION STATION TO STATION			LENGTH (FT)	WIDTH (FT)	PAVEMENT REMOVAL (SQ YD)	PCC PAVEMENT 10" (SQ YD)	AGGREGATE BASE CSE., TY. A 6" (SQ YD)	PAVEMENT FABRIC (SQ YD)	PROTECTIVE COAT (SQ YD)
FAP 331 - MAINLINE									
URBAN LIMITS									
620+45.00	TO	627+77.00	732	24	1952.0	1952	1952	1952	1952
PROJECT TOTALS					1952.0	1952.0	1952.0	1952.0	1952.0

PLOT DATE = 4/9/2009
FILE NAME = c:\pw_pw01\wf0025877\sf0025877mm02.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = mooorder