

PAINT PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION				PAINT PAVEMENT MARKING					
				LINE - 4" YELLOW			LINE - 4" WHITE	LINE - 24" WHITE	LETTERS AND SYMBOLS
				LEFT SOLID	CENTER DASHED	RIGHT SOLID	SOLID	SOLID	WHITE
				FEET	FEET **	FEET	SQ FT		
STA. 120+91	TO	STA. 131+06		253.75		2030			
STA. 131+06	TO	STA. 142+75		292.25	1169	2338			
STA. 142+75	TO	STA. 149+58	683		683	1366			
STA. 149+58	TO	STA. 153+41.33 BK =	383.3	95.8		766.6			
STA. 153+99.30 A	TO	STA. 160+25	625.7	156.4		1,251.4			
STA. 160+25	TO	STA. 173+06		320.3		2,562.0			
STA. 173+06	TO	STA. 182+77		242.8	971.0	1,942.0			
STA. 182+77	TO	STA. 188+71.88 BK =	594.9		594.9	1,189.8			
STA. 187+45.50 A	TO	STA. 194+60	714.5		714.5	1,429.0			
STA. 194+60	TO	STA. 205+25	1,065.0	266.3		2,130.0			
STA. 205+25	TO	STA. 209+22		99.3		794.0			
STA. 209+22	TO	STA. 219+04		245.5	982.0	1,964.0			
STA. 219+04	TO	STA. 220+40	136.0		136.0	272.0			
STA. 220+40	TO	STA. 222+94.85 BK =	254.8	63.7		509.6			
STA. 223+03.90 A	TO	STA. 230+91	787.1	196.8		1,574.2			
STA. 230+91	TO	STA. 269+82		972.8		7,782.0			
STA. 269+82	TO	STA. 276+27		161.3	645.0	1,290.0			
STA. 276+27	TO	STA. 279+12		71.3	285.0				
STA. 279+12	TO	STA. 280+34	122.0		122.0				
STA. 280+34	TO	STA. 287+67	733.0	183.3		6.0			
STA. 287+67	TO	STA. 289+37	170.0	42.5		340.0			
STA. 289+37	TO	STA. 290+36		24.8		198.0			
STA. 290+36	TO	STA. 305+32		374.0		9.0			
STA. 305+32	TO	STA. 338+88		839.0		6,712.0			
STA. 338+88	TO	STA. 346+14		181.5	726.0	1,452.0			
STA. 346+14	TO	STA. 348+43	229.0		229.0	458.0			
STA. 348+43	TO	STA. 348+93	50.0	12.5		100.0			
STA. 348+93	TO	STA. 357+82	889.0	222.3					
STA. 357+82	TO	STA. 362+84		125.5		81.0			
STA. 362+84	TO	STA. 385+43		564.8		4,518.0			
STA. 385+43	TO	STA. 390+25		120.5	482.0	964.0			
STA. 390+25	TO	STA. 394+47		105.5		844.0			
STA. 394+47	TO	STA. 399+33	486.0	121.5		972.0			
STA. 399+33	TO	STA. 399+56.83 BK =		6.0		47.7			
STA. 0+00 AH	TO	STA. 34+29		857.3		6,858.0			
STA. 34+29	TO	STA. 38+48		104.8		419.0			
STA. 38+48	TO	STA. 42+41.29 BK =		98.3	393.3	393.3			
STA. 44+46.2 AH	TO	STA. 45+37		22.7	90.8	90.8	12.0		
STA. 45+37	TO	STA. 49+93	456.0	114.0		912.0	61.2 *		
STA. 49+93	TO	STA. 51+32	139.0	34.8		278.0	12.0		
STA. 51+32	TO	STA. 52+66	134.0		134.0	268.0			
STA. 52+66	TO	STA. 59+40		168.5	674.0	1,348.0			
STA. 59+40	TO	STA. 60+74	134.0		134.0	268.0			
STA. 60+74	TO	STA. 62+28.48 BK =	154.5	38.6		309.0			
STA. 62+77.20 AH	TO	STA. 70+16	738.8	184.7		1,477.6			
STA. 70+16	TO	STA. 70+46		7.5		60.0			
STA. 70+46	TO	STA. 80+53	1,007.0	251.8		2,014.0			
STA. 80+53	TO	STA. 84+46	393.0		393.0	786.0			
STA. 84+46	TO	STA. 86+03.40 BK =	157.4		157.4	314.8			
STA. 39+77.20 AH	TO	STA. 47+69	791.8		791.8	1,583.6			
STA. 47+69	TO	STA. 192+32		3,615.8		28,926.0			
SUBTOTAL				12,028.8	11,860.1	10,507.7	94,198.3	24.0	0.0
TOTAL					128,595			24	0.0

* RR crossing symbols
 ** Accounts for double edge line striping

FILE NAME = c:\pro\jocote\78044\78044-mscd.dgn	USER NAME = ccolem	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.P. RTE. 726	SECTION (119,120)RS-3	COUNTY JEFFERSON	TOTAL SHEETS 16	SHEET NO. 5
PLOT SCALE = 1/8" = 100.0000' / IN.		DRAWN -	REVISED -							
PLOT DATE = 3/13/2008		CHECKED -	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
		DATE -	REVISED -						CONTRACT NO. 78044	