

# SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	CONSTRUCTION TYPE CODE	
		UNIT	TOTAL QUANTITIES 1000 90 % FED 10 % STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	22
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	10
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	188
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	141
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	141
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.4
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	1.2
25100120	MULCH, METHOD 2	TON	2.4
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120
28000400	PERIMETER EROSION BARRIER	FOOT	2,191
28000600	SEEDING, CLASS 7	ACRE	1.2
28100105	STONE RIPRAP, CLASS A3	SQ YD	631
28102600	STONE RIPRAP DITCH	TON	517
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8,243
40600300	AGGREGATE (PRIME COAT)	TON	140
40600400	MIXTURES FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	720
40600990	TEMPORARY RAMP	SQ YD	86
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	9,092
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	4,879
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	44,255
44050160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	249
44000162	HOT MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	12,427
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,098
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SQ YD	7
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,751
48203010	HOT-MIX ASPHALT SHOULDERS, 3 1/4"	SQ YD	33,733
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	225
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	232
63500105	DELINEATORS	EACH	56
63500120	DELINEATOR REMOVAL	EACH	49
64200105	SHOULDER RUMBLE STRIP	FOOT	43,370
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	0.5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,712
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	48,792
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	20,168
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	48,792
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	48
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	271
* 78200420	GUARDRAIL MARKER, TYPE B	EACH	3
* 78201000	TERMINAL MARKER- DIRECT APPLIED	EACH	1
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	271
X0322729	MATERIAL TRANSFER DEVICE	TON	13,971

\*SPECIALTY ITEMS

FILE NAME = c:\projects\78051\78051-sch.dgn	USER NAME = carlsonaj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 57	SECTION 77-12,3RS	COUNTY PULASKI	TOTAL SHEETS 19	SHEET NO. 3
PLOT SCALE = 50.0000' / IN.		DRAWN -	REVISED -			SCALE:		SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 78051
PLOT DATE = 3/18/2008		CHECKED -	REVISED -			FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		DATE -	REVISED -							