

PAVEMENT MARKING

LOCATION STATION TO STATION	POLYUREA PAVEMENT MARKING TYPE I, LINE - 4"		POLYUREA PAVEMENT MARKING TYPE I, LINE - 12"	POLYUREA PAVEMENT MARKING TYPE I, LINE - 24"	POLYUREA PAVEMENT MARKING TYPE I LTR & SYM
	SOLID YELLOW	SOLID WHITE			
	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
IL 149					
676+07, LT				12	
677+17, LT				12	
KEN GRAY BLVD.					
10+35, LT.				25	
10+36 TO 11+81.1, 16.0' LT.		121			
10+50 LT. (RT. ARROW)					8.8
10+56 TO 11+81.1	518		66		
10+58, LT.				16	
10+80 LT. (LT. / THROUGH)					14.7
11+15 LT. (ONLY)					11.8
11+23 LT. (ONLY)					11.8
11+81.1 TO 678+28.27		225	281		
11+81.1 TO 678+28.27		175			
11+93 LT. (LT. / THROUGH)					14.7
11+93 LT. (RT. ARROW)					8.8
SUBTOTALS	518	521			
TOTALS	1039		347	65	70.6

REMOVAL SCHEDULE

LOCATION STATION TO STATION	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	PAVEMENT MARKING REMOVAL
KEN GRAY BLVD.	SQ YD	FOOT	FOOT
675+55 TO 676+19, 26' LT IL 149 E.B.			64
677+21 TO 678+28, 26' LT IL 149 E.B.			107
10+26.00 TO 11+81.1	953		
10+31.01, 56.77' LT TO 10+42.76, 43.01' LT		18.4	
10+32.45, 38.95' RT TO 11+81.10, 22.00' RT		201.9	
10+98.29, 36.71' LT TO 11+81.10, 32.80' LT		55	
TOTALS	953	275	171

DRAINAGE SCHEDULE

LOCATION STATION TO STATION	COMB. CC&G TYPE B-6.24	INLETS SPECIAL TYPE 3 6 FOOT	CONCRETE COLLAR	PIPE CULVERTS CLASS A TYPE 1 54"	PRECAST REINFORCED CONCRETE FLARED END SECTION 54"	STORM SEWERS CLASS A TYPE 1 15"	PRECAST REINFORCED CONCRETE FLARED END SECTION 15"	TRENCH BACKFILL	PROTECTIVE COAT
KEN GRAY BLVD.	FOOT	EACH	CU YD	FOOT	EACH	FOOT	EACH	CU YD	
675+69.46, 30.0' RT (IL 149EB) TO 11+81.1, 22.0' RT (KEN GRAY BLVD.)	222								62
11+81.1, 34.0' LT (KEN GRAY BLVD.) TO 677+68.06, 35.0' RT (IL 149EB)	108								30
10+61.97, 39.12 LT TO 11+93.85, 65.94' LT				56					
10+62.1, 39.1' LT TO 10+61.5, 63.7' LT							14		
10+62.14, 39.13' LT			0.71						
10+62.60, 26.35' RT			0.71						
10+62.74, 25.9' RT TO 10+62.74, 34.4 RT							5		
10+62.82, 60.22' RT TO 10+62.73, 26.34 RT				34					
10+62.83, 68.55' RT					1				
10+72.95, 24.45' RT TO 11+22.01, 52.11' LT						81	14		
10+73.0, 23.86' RT		1							
11+20.0, 51.74' LT		1							
11+36.74, 52.84' LT TO 11+96.11, 58.72' LT						37			
12+02.18, 66.07' LT					1				
12+02.16, 59.47 LT							1		
TOTALS	330	2	1.42	90	2	118	33		92