

PAVING SCHEDULE

LOCATION STATION TO STATION	SUB-BASE GRANULAR MATERIAL TYPE A 4"	PORTLAND CEMENT CONCRETE PVMNT 10" (JOINTED)	HOT-MIX ASPHALT SHOULDERS 8"	PROTECTIVE COAT
	SQ YD	SQ YD	SQ YD	SQ YD
674+48.64 TO 675+69.46 (IL 149 E.B.)			53	
677+68.06 TO 679+30.00 (IL 149 E.B.)			168	
10+26.00 TO 11+81.1 (KEN GRAY BLVD.)	1416	1267		1267
TOTALS	1416	1267	221	1267

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD
KEN GRAY BLVD.				
10+26.00 TO 11+81.10	126	95	423	328
TOTALS	126			-328

25% SHRINKAGE FOR EARTH EXCAVATION

SEEDING AND EROSION CONTROL

LOCATION STATION TO STATION	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	SEEDING CLASS 1B	SEEDING CLASS 7	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	EROSION CONTROL BLANKET	INLET AND PIPE PROTECTION	STONE RIP RAP CLASS A4	FILTER FABRIC
	POUND	POUND	POUND	ACRE	ACRE	TON	ACRE	SQ YD	EACH	SQ YD	SQ YD
KEN GRAY BLVD.											
10+26.00 TO 11+81.10	40	30	30	0.25	0.25	0.5	0.5	516			
10+63, 72.0' RT									1		
12+05, 66' LT										19	19
TOTALS	40	30	30	0.25	0.25	0.5	0.5	516	1	19	19

STAGING PAVEMENT MARKING

LOCATION STATION TO STATION	TEMPORARY PAVEMENT MARKING -				TEMPORARY PAVEMENT MARKING TAPE, 6 INCH (BLACK) FOOT	
	LINE 4" (SPECIAL)		LINE 24" (SPECIAL)			LETTERS AND SYMBOLS (SPECIAL)
	YELLOW FOOT	WHITE FOOT	WHITE FOOT	WHITE SQ YD		WHITE SQ YD
KEN GRAY BLVD.						
STAGE 2						
10+35 TO 11+60 19' LT			125			
10+55 TO 12+20 8' LT & TAPER (DOUBLE)	300					
TH/LT ARROW AND ONLY				37.8		
RT ARROW AND ONLY				27.4		
STAGE 3						
10+55 TO 12+60 16' LT AND TAPER			180			
LT/TH/RT ARROW				38.4		
3 LT/TH ARROWS					156	
STAGE 4						
10+35 RT TURN LANE (STOP BAR)					300	
10+35 TO 12+50 16' LT					215	
10+55 LT/TH LANE (STOP BAR)					64	
10+60 LT			34			
10+60 TO 13+30 25' LT (DOUBLE)	480					
LT/TH/RT ARROW				38.4		
2 RT ARROWS					62.4	
STAGE 5						
10+55 TO 12+50 C/L (DOUBLE)					390	
10+60 TO 12+20 13' RT (DOUBLE)	320					
10+60 13' RT TO 5' LT			18			
SUBTOTALS	1100	305				
TOTALS		1405	52	142.0	1187	

FILE NAME =	USER NAME = possl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\projects\78055\978055_eht.miso.dgn		DRAWN -	REVISED -			873	(28-5) TS-3,N-1	FRANKLIN	38	8	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 78055					
PLOT DATE = 3/19/2009		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					