CONTRACT NO. 85427

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-BT	ROCK ISLAND	112	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FED 20% CITY J000 P.C. CONCRETE	80% FED 20% OTHER Y046 P.C. PATH	80% FED 20% OTHER SFTY-2A STRUCTURES	80% FED 20% CITY Y007 MINOR STRUCT.	80% FED 20% OTHER Y007 MINOR STRUCT.	80% FED 20% CITY Y030-1E HWY. LIGHTING	80% FED 20% OTHER Y030-1E HWY. LIGHTING
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	50	50						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL.	39.4	39.4						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	17.6	17.6						
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	S.Y.	321	321						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	S.F.	10,331	4,295	6,636					
42400800	DETECTABLE WARNINGS	S.F.	60	60						
44000100	PAVEMENT REMOVAL	S.Y.	69	69						
44000200	DRIVEWAY PAVEMENT REMOVAL	S.Y.	22	22						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	120	120						
44000600	SIDEWALK REMOVAL	S.F.	4,020	684	3,336					
44213200	SAW CUTS	FOOT	98	98						
50200100	STRUCTURE EXCAVATION	C.Y.	57.4			57.4				
50300225	CONCRETE STRUCTURES	C.Y.	64.1			64.1				
50300255	CONCRETE SUPERSTRUCTURE	C.Y.	18.6			18.6				
50300300	PROTECTIVE COAT	S.Y.	89			89				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L.SUM	1			1				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5,360					5,360		
50500505	STUD SHEAR CONNECTORS	EACH	786			642		144		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	30,190			30,190				
50901725	BICYCLE RAILING, SPECIAL	FOOT	295			140		155		
50901760	PIPE HANDRAIL	FOOT	22.8		22.8					
51204900	STEEL SHEET PILING	S.F.	4,340					4,340		
*SPECIALTY ITEMS										

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $IFILE$
PLOT SCALE = $SCALE$
USER NAME = $USERN$