

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-B1	ROCK ISLAND	112	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT
11TH AVENUE	
9' LT. STA. 1+97	9
23' LT. STA. 2+24	6
4' LT. STA. 2+97	12
0' LT. STA. 3+61	10
3' RT. STA. 3+61	10
1' LT. STA. 3+74	10
2' LT. STA. 4+25	12
MULTI-USE PATH	
14' LT. STA. 101+26	6
14' LT. STA. 101+48	6
15' LT. STA. 101+63	12
2' RT. STA. 102+05	12
12' RT. STA. 102+77	6
1' RT. STA. 102+78	6
8' LT. STA. 102+80	15
10' RT. STA. 102+87	6
5' RT. STA. 103+98	12
7' RT. STA. 104+03	6
8' RT. STA. 104+11	12
10' RT. STA. 104+34	8
6' LT. STA. 104+52	6
2' RT. STA. 104+73	10
7' RT. STA. 104+77	10
9' RT. STA. 104+92	8
12' RT. STA. 104+96	6
2' RT. STA. 105+03	6
2' LT. STA. 105+03	6
10' RT. STA. 105+12	6
4' LT. STA. 105+30	6
6' LT. STA. 105+38	6
8' RT. STA. 105+63	6
3' RT. STA. 105+64	8
2' LT. STA. 106+15	6
6' RT. STA. 106+20	12
1' LT. STA. 106+24	6
2' RT. STA. 106+26	6
2' LT. STA. 106+33	6
3' RT. STA. 106+50	6
10' RT. STA. 106+65	14
11' RT. STA. 106+66	6
12' RT. STA. 106+78	12
13' RT. STA. 106+83	12
NATURE TRAIL	
RT. 1.32' OFFSET, STA. 200+49.26	12
LT. 4.89' OFFSET, STA. 200+20.73	10
RT. 3.32' OFFSET, STA. 200+83.18	10
LT. 4.64' OFFSET, STA. 200+89.85	12
RT. 1.60' OFFSET, STA. 201+31.84	10
RT. 0.23' OFFSET, STA. 201+47.30	6
RT. 3.11' OFFSET, STA. 202+18.19	8
LT. 4.88' OFFSET, STA. 203+01.41	12
TOTAL	428
20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT
11TH AVENUE	
23' LT. STA. 1+73	36
16' LT. STA. 1+75	33
10' LT. STA. 1+77	24
26' LT. STA. 2+09	18
25' LT. STA. 2+10	18
4' RT. STA. 3+20	24
3' RT. STA. 3+29	18
4' LT. STA. 3+51	24
1' LT. STA. 3+77	48
19' RT. STA. 4+77	24
MULTI-USE PATH	
11' LT. STA. 102+45	30
10' LT. STA. 102+46	36
3' RT. STA. 102+74	20
10' RT. STA. 104+39	18
11' RT. STA. 105+68	18
7' LT. STA. 105+82	24
24' LT. STA. 105+98	16
8' LT. STA. 105+99	48
NATURE TRAIL	
RT. 7.31' OFFSET, STA. 202+07.17	20
TOTAL	497

20700220 POROUS GRANULAR EMBANKMENT	C. Y.
MULTI-USE PATH	
LT. STA. 101+25-102+72.43 (RETAINING WALL)	310
TOTAL	310
20800150 TRENCH BACKFILL	C. Y.
STORM SEWER	
11TH AVENUE	
LT./RT. STA. 2+85	6.2
LT. STA. 2+85 TO 2+93	7.9
LT. STA. 2+93 TO RT. STA. 3+88	87.8
17' LT. STA. 3+03 TO 13' RT. STA. 3+19 (STORM SEWER REMOVAL)	18.2
37TH STREET	
RT. STA. 9+93 TO 10+32	6.0
LT./RT. STA. 10+32	3.0
RT. STA. 10+32 (37TH STREET) TO LT. STA. 2+93 (11TH AVENUE)	77.8
15' RT. STA. 10+04 TO 15' LT. STA. 10+69 (STORM SEWER REMOVAL)	12.5
WATER MAIN	
11TH AVENUE	
STA. 0+86 TO 4+92	205.7
LT./RT. STA. 1+91	20.8
LT./RT. STA. 4+92	11.2
RT. STA. 5+40	1.2
RT. STA. 5+42.5	1.2
37TH STREET	
RT. STA. 9+89 (37TH STREET) TO LT. STA. 3+52 (11TH AVE.)	74.0
SANITARY SEWER	
11TH AVENUE	
RT. STA. 0+60 TO STA. 2+25	84.9
RT. STA. 2+25 TO STA. 3+22	10.0
RT. STA. 1+06	7.3
RT. STA. 2+23	2.1
37TH STREET	
STA. 10+82 TO 10+92	1.0
LT. STA. 10+00.9 TO STA. 10+93	7.8
TOTAL	646.6
21001000 GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	S. Y.
11TH AVENUE	
STA. 0+57.42 TO 1+07.60	116
STA. 1+07.60 TO 6+23.92	1,717
37TH STREET	
STA. 9+91.60 TO 11+00.04	379
TOTAL	2,212
25000300 SEEDING, CLASS 3	ACRE
11TH AVENUE	
90' LT. STA. 2+13-23' LT. STA. 2+92	0.02
NATURE TRAIL	
RT. STA. 200+00-205+00	0.04
LT. STA. 200+00-205+00	0.05
TOTAL	0.11
25000400 NITROGEN FERTILIZER NUTRIENT	POUND
11TH AVENUE	
90' -23' LT. STA. 2+13-2+92	2
NATURE TRAIL	
LT. & RT. STA. 200+00-205+00	6
TOTAL	8

25000500 PHOSPHORUS FERTILIZER NUTRIENT	POUND
11TH AVENUE	
90' -23' LT. STA. 2+13-2+92	2
NATURE TRAIL	
LT. & RT. STA. 200+00-205+00	6
TOTAL	8
25000600 POTASSIUM FERTILIZER NUTRIENT	POUND
11TH AVENUE	
90' -23' LT. STA. 2+13-2+92	2
NATURE TRAIL	
LT. & RT. STA. 200+00-205+00	6
TOTAL	8
25100115 MULCH, METHOD 2	ACRE
11TH AVENUE	
LT. & RT. STA. 0+55-6+19	0.19
37TH STREET	
LT. & RT. STA. 9+89-10+92	0.02
MULTI-USE PATH	
LT. & RT. STA. 100+25-103+00	0.08
LT. & RT. STA. 106+75-107+90	0.04
LT. & RT. STA. 103+00-106+75	0.46
TOTAL	0.79
25100635 HEAVY DUTY EROSION CONTROL BLANKET	S. Y.
11TH AVENUE	
90' -23' LT. STA. 2+13-2+92	97
NATURE TRAIL	
LT. & RT. STA. 200+00-205+00	436
TOTAL	533
25100900 TURF REINFORCEMENT MAT	S. Y.
11TH AVENUE	
92' LT. STA. 2+12	11.1
MULTI-USE PATH	
15' LT. STA. 105+00-105+23	22.7
NATURE TRAIL	
12' RT. STA. 202+16	22.2
TOTAL	56.0
25101504 WOOD CHIP MULCH, 4"	S. Y.
NATURE TRAIL	
LT. & RT. STA. 200+00-205+00	262
TOTAL	262

PLT DATE * DRAWN
FILE NAME * PLOT
PLOT SCALE * RESCALE
USER NAME * RUBEN

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DRAWN BY _____
CHECKED BY _____