

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-BT	ROCK ISLAND	112	20
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

25200100 SODDING	S. Y.	28000500 INLET AND PIPE PROTECTION	EACH	42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	S. F.
11TH AVENUE		11TH AVENUE		11TH AVENUE	
RT. STA. 0+55-3+20	151.8	LT. & RT. STA. 2.87	2	LT. STA. 1+01.55 TO 3+10.18	821
LT. STA. 0+55-3+10	160.8	RT. STA. 3.87	1	LT. STA. 3+10.18 TO 3+20.18	183
RT. STA. 3+67-6+19	101.7			LT. STA. 3+20.18 TO 5+87.33	1,015
LT. STA. 3+20-6+04	423.7	37TH STREET		LT. STA. 5+21	28
		RT. STA. 9+94	1	LT. STA. 5+55.5	32
37TH STREET		LT. & RT. STA. 10+32	2	LT. STA. 5+97.98 TO 6+20.28	205
RT. STA. 9+89-10+92	62.2			RT. STA. 1+25.25 TO 3+24.52	754
LT. STA. 9+89-10+90	53.3	NATURE TRAIL		RT. STA. 3+67.58 TO 6+23.13	753
		RT. STA. 200+10	1		
MULTI-USE PATH		LT. STA. 202+30	1	MULTI-USE PATH	
RT. STA. 100+25-103+00	303.0			STA. 100+30.06 TO 102+72.43	2,424
LT. STA. 100+25-103+00	77.5	31100100 SUB-BASE GRANULAR MATERIAL, TYPE A	TON	STA. 106+97.02 TO 107+48.34	513
RT. STA. 106+75-107+71	60.0			STA. 107+48.34 TO 107+98	1,004
LT. STA. 106+75-107+90	74.0	11TH AVENUE		104' RT. STA. 107+54 TO 169' RT. STA. 107+33	397
		STA. 1+07.60 TO 6+23.92	587	162' RT. STA. 107+63 TO 246' RT. STA. 107+52	1,071
TOTAL	1,468.0	37TH STREET			1,004
		STA. 9+91.60 TO 11+00.04	130	DORMITORY STAIRS	
25200200 SUPPLEMENTAL WATERING	UNIT			STA. 0+11.42 TO 0+22+11	79
11TH AVENUE		35100100 AGGREGATE BASE COURSE, TYPE A	TON	STA. 0+31.31 TO 0+53.93	144
LT. & RT. STA. 0+55-6+19	17.6			37TH STREET	
		11TH AVENUE		LT. STA. 9+63.07 TO 10+34.64	358
37TH STREET		STA. 0+57.42 TO 1+07.60	79	LT. STA. 10+61.33 TO 10+90.40	146
LT. & RT. STA. 9+89-10+92	2.4			TOTAL	10,931
		40200800 AGGREGATE SURFACE COURSE, TYPE B	TON		
MULTI-USE PATH		FOR TEMPORARY ACCESS AS NEEDED	50	42400800 DETECTABLE WARNINGS	S. F.
LT. & RT. STA. 100+25-107+90	10.8			11TH AVENUE	
				LT. STA. 3+15.18	20
TOTAL	30.8	40600100 BITUMINOUS MATERIALS (PRIME COAT)	GAL	RT. STA. 3+18 (2 CURB RAMPS)	16
				RT. STA. 3+74	8
28000250 TEMPORARY EROSION CONTROL SEEDING	POUND	11TH AVENUE		LT. STA. 6+10	16
11TH AVENUE		STA. 0+57.42 TO 1+07.60	79	RT. STA. 6+10	16
LT. & RT. STA. 0+55-6+19	76			TOTAL	60
		40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON		
37TH STREET				44000100 PAVEMENT REMOVAL	S. Y.
LT. & RT. STA. 9+89-10+92	8	11TH AVENUE		11TH AVENUE	
		STA. 0+57.42 TO 1+07.60	39.4	STA. 6+02 TO 6+24	49
MULTI-USE PATH				37TH STREET	
LT. & RT. STA. 100+25-103+00	32	42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	S. Y.	STA. 9+87 TO 9+99	20
LT. & RT. STA. 106+75-107+90	16			TOTAL	69
LT. & RT. STA. 103+0-106+75	184	11TH AVENUE		44000200 DRIVEWAY PAVEMENT REMOVAL	S. Y.
		STA. 0+57.42 TO 1+07.60	17.6	37TH STREET	
TOTAL	316			RT. STA. 10+31	22
		40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	TOTAL	22
28000300 TEMPORARY DITCH CHECKS	EACH			44000500 COMBINATION CURB AND GUTTER REMOVAL	FT.
NATURE TRAIL		11TH AVENUE		11TH AVENUE	
LT. STA. 200+50	1	LT. STA. 0+95.94	49	LT. STA. 6+02 TO 6+24	61
LT. STA. 201+00	1	RT. STA. 1+12.99	35	RT. STA. 6+02 TO 6+24	39
LT. STA. 201+50	1	RT. STA. 1+95.24	44		
LT. STA. 202+00	1	RT. STA. 4+93.32	21	37TH STREET	
		RT. STA. 5+19.94	30	LT. STA. 9+91.6 TO 10+03.6	12
TOTAL	4	RT. STA. 5+75.65	44	RT. STA. 9+91.84 TO 9+99.4	8
		37TH STREET		TOTAL	120
28000400 PERIMETER EROSION BARRIER	FT.				
11TH AVENUE		11TH AVENUE			
LT. STA. 1+00-3+00	200	LT. STA. 0+95.94	49		
LT. STA. 3+25-5+30	205	RT. STA. 1+12.99	35		
		RT. STA. 1+95.24	44		
MULTI-USE PATH		RT. STA. 4+93.32	21		
LT. STA. 100+25-103+00	275	RT. STA. 5+19.94	30		
RT. STA. 100+25-101+50	125	RT. STA. 5+75.65	44		
RT. STA. 102+65-103+00	45	37TH STREET			
LT. STA. 105+00-107+90	350	RT. STA. 10+31.00	56		
RT. STA. 106+80-106+92	12	LT. STA. 10+48.08	42		
NATURE TRAIL					
LT. STA. 200+00-200+72	72				
RT. STA. 200+72-201+44	72				
LT. STA. 201+20-202+70	150				
RT. STA. 202+07-205+00	293				
LT. STA. 203+60-205+00	140				
TOTAL	1,939				

PLT DATE: 04/25/07  
 FILE NAME: 050174-00-BT  
 PLOT SCALE: 1/8"=1'-0"  
 USER NAME: RUSSEN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_