CONTRACT NO. 85427

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-BT	ROCK ISLAND	112	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

78001110 PAINT PAVEMENT MARKING, LINE 4"		FT.
SOLID WHITE		
11TH AVENUE		
LT./RT. STA. 3+13		28.5
LT./RT. STA. 3+19		32.2
LT./RT. STA. 6+07.4		34.1
LT./RT. STA. 6+13.4		43.0
	TOTAL	137.8
80400100 ELECTRIC SERVICE INSTALLATION		EACH
37TH STREET		
LT. STA. 9+94		1
	TOTAL	1
81400730 HANDHOLE, COMPOSITE CONCRETE		EACH
11TH AVENUE		
LT. STA. 3+90		1
LT. STA. 5+05		1
	TOTAL	2
82103150 LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 150 WATT		EACH
11TH AVENUE		
RT. STA. 1+33		1
RT. STA. 3+06		1
RT. STA. 6+02		1
	TOTAL	3
83600100 LIGHT POLE FOUNDATION		EACH
11TH AVENUE		
LT. STA. 1+25		1
LT. STA. 1+46		1
LT. STA. 1+66		1
LT. STA. 1+86		1
LT. STA. 2+06		1
LT. STA. 2+26		1
LT. STA. 2+46		1
LT. STA. 2+65		1
LT. STA. 2+86		1
LT. STA. 3+06		1
LT. STA. 3+28		1
LT. STA. 3+49		1
LT. STA. 3+69		1
LT. STA. 3+90		1
	TOTAL	14
83600110 LIGHT POLE FOUNDATION (SPECIAL)		EACH
11TH AVENUE		
RT. STA. 1+33		1
RT. STA. 3+06		1
RT. STA. 6+02		1
MULTI-USE PATH		
RT. STA. 100+25 (BLUE PHONE)		1
RT. STA. 100+55		1
RT. STA. 101+22		1
RT. STA. 101+94		1
RT. STA. 102+70		1
RT. STA. 106+97		1
RT. STA. 107+45		1
LT. STA. 108+12 (BLUE PHONE)		1
	TOTAL	11
84200700 LIGHTING FOUNDATION REMOVAL		EACH
MULTI-USE PATH		
LT. STA. 106+04		1
LT. STA. 106+61		1
LT. STA. 107+19		1
	TOTAL	3

Z0015500 DEBRIS REMOVAL		L. SUM
NATURE TRAIL		
LT. & RT. STA. 200+00-205+00		1
	TOTAL	1
Z0075500 TIMBER RETAINING WALL		S.F.
NATURE TRAIL		
4.5' LT. STA. 200+40-201+44		581
4.5' RT. STA. 200+72-201+20		224
4.5' RT. STA. 201+90-202+07		112
4.5' RT. STA. 202+70-202+36		299
4.5' LT. STA. 202+70-202+36		277
	TOTAL	1,493
Z0076600 TRAINEES		HOUR
ENTIRE PROJECT		500
	TOTAL	500
XX000679 CUT AND CAP EXISTING WATER MAIN		EACH
11TH AVENUE		
3' RT. STA. 6+21		1
	TOTAL	1
XX000739 CURB STOP & BOX 1 INCH		EACH
11TH AVENUE		
16' RT. STA. 1+64		1
15' RT. STA. 4+57		1
37TH STREET		
16' RT. STA. 10+63.5		1
	TOTAL	3
XX003182 BOLLARDS COMPLETE (SET OF 3)		EACH
MULTI-USE PATH		
STA. 102+19		1
	TOTAL	1
XX003519 DUCTILE IRON WATER MAIN FITTING - 12" X 6" TEE		EACH
11TH AVENUE		
12' RT. STA. 5+40		1
	TOTAL	1
XX003526 DUCTILE IRON WATER MAIN FITTING - 8" X 6" REDUCER		EACH
11TH AVENUE		
39.5' RT. STA. 1+93		1
37TH STREET		
1' LT. STA. 9+89		1
	TOTAL	2
XX003539 DUCTILE IRON WATER MAIN FITTINGS 8" X 6" TEE		EACH
37TH STREET		
3.6' RT. STA. 9+95.6		1
	TOTAL	1
XX003542 DUCTILE IRON WATER MAIN FITTINGS 6" 45 DEGREE BEND		EACH
37TH STREET		
2' RT. STA. 9+98		1
	TOTAL	1

XX003543 DUCTILE IRON WATER MAIN FITTINGS 8" 45 DEGREE BEND		EACH
11TH AVENUE		
8' LT. STA. 0+86 (HORIZONTAL BEND)		1
15.58' LT. STA. 0+96 (HORIZONTAL BEND)		1
37.5' RT. STA. 1+91 (HORIZONTAL BEND)		1
39.5' RT. STA. 1+93 (HORIZONTAL BEND)		1
6' RT. STA. 4+92 (VERTICAL BENDS)		2
37TH STREET		
1' LT. STA. 9+89 (HORIZONTAL BEND)		1
9.6' RT. STA. 10+00 (HORIZONTAL BEND)		1
0.5' LT. STA. 10+00.9 (SAN. S.)		1
20.3' LT. STA. 10+20.8 (SAN. S.)		1
	TOTAL	10
XX003788 BEND, DUCTILE IRON MECHANICAL JOINT 90 DEGREES, 8"		EACH
11TH AVENUE		
15.58' LT. STA. 4+92		1
	TOTAL	1
XX003795 VALVE GATE, 8" MJRW & BOX		EACH
11TH AVENUE		
11.6' LT. STA. 1+91		1
13' RT. STA. 4+92		1
37TH STREET		
1' LT. STA. 9+89		1
	TOTAL	3
XX003796 TAP & CORP, 1"		EACH
11TH AVENUE		
15.58' LT. STA. 1+64		1
15.58' LT. STA. 4+57		1
37TH STREET		
9.6' RT. STA. 10+63.5		1
	TOTAL	3
XX003799 COPPER SERVICE, TYPE K 1"		FT.
11TH AVENUE		
LT./RT. STA. 1+64		40
LT./RT. STA. 4+57		40
37TH STREET		
RT. STA. 10+63.5		16
	TOTAL	96
XX004951 CONCRETE STAIRS		L. SUM
DORMITORY STAIRS		
STA. 0+22.11 TO 0+31.31		1
	TOTAL	1
XX005355 STEEP SLOPE VEGETATION, SPECIAL		S.Y.
MULTI-USE PATH		
STA. 102+90-106+50		2,200
	TOTAL	2,200

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $PSCALE$
USER NAME = $USERN$