

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00334-00-SW	MCLEAN	13	C1.1
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

PAY CODE	ITEMS	UNIT	QUANTITY
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	22
* 20200100	EARTH EXCAVATION	CU YD	110
* 20800150	TRENCH BACKFILL	CU YD	220
28000500	INLET AND PIPE PROTECTION	EACH	4
* 31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	90
* 35300200	P.C.C. BASE COURSE 7"	SQ YD	260
* 40603310	HOT MIX ASPHALT SURF CRSE. MIX C. N50	TON	50
* 42300200	P.C.C. DRIVEWAY PAVEMENT, 6"	SQ YD	80
42400800	DETECTABLE WARNINGS	SQ FT	30
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	85
* 44000600	SIDEWALK REMOVAL	SQ FT	4,750
550A0340	STORM SEWER, CLASS A, TYPE 2, 12"	FOOT	60
550B0040	STORM SEWER, CLASS B, TYPE 1, 10"	FOOT	10
* 60228400	MANHOLES, SPECIAL	EACH	1
* 60235700	INLETS, TYPE A, TYPE 3 FRAME & GRATE	EACH	2
* 60255500	MANHOLES TO BE ADJUSTED	EACH	6
* 60260100	INLETS TO BE ADJUSTED	EACH	2
* 60266600	VALVE BOXES TO BE ADJUSTED	EACH	6
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	48
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	275
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30
81012600	CONDUIT IN TRENCH, 2" PVC	FOOT	1,500
* 81400105	HANDHOLE (SPECIAL)	EACH	9
81702120	ELECTRICAL CABLE IN CONDUIT 600V (XLP-TYPE USE) 1/2" NO. 8	FOOT	3,920
* 83600100	LIGHT POLE FOUNDATION	EACH	7
* 70013798	CONSTRUCTION LAYOUT	L SUM	1
* B2005720	TREE, PYRUS CALLERYANA CHANTICLEER CHANTICLEER GALLERY PEAR, 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2
* K1005481	SHREDDED BARK MULCH, 3"	SQ YD	1
* XX001011	BICYCLE RACKS	EACH	2
* XX005420	ULMUS PARVIFOLIA 'FRONTIER' (FRONTIER CHINESE ELM) 2-1/2 CAL	EACH	1
* XX005819	INLET TYPE A1, SPECIAL	EACH	1
* XX006429	SIDEWALK, SPECIAL	SQ FT	4,750
* X0324994	ORNAMENTAL PLANTER	L SUM	16
* X0444100	BENCHES	EACH	7
* X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CU YD	9
* X5011100	CONCRETE FOUNDATION REMOVAL	EACH	2
X8250400	LIGHTING CONTROLLER, PEDESTAL MOUNT	EACH	1
XX007300	STRAWBERRY CANDY DAYLILY	EACH	36
* XX007361	LIGHT 445 WATT FLUORESCENT	EACH	2
* XX007362	LIGHT 105 WATT FLUORESCENT	EACH	5
XX007363	COMPOST FURNISH AND PLACE, SPECIAL	CU YD	3

\* SPECIAL PROVISION

PLUT DATE \* DATE \*  
 PLUT SCALE \* SCALE \*  
 USER NAME \* USER

REVISIONS	
NAME	DATE
ADDENDUM #1	5-21-08
REV. ADDENDUM #1	5-29-08
	6-3-08

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 CITY OF BLOOMINGTON  
 DOWNTOWN MAIN STREET BEAUTIFICATION  
 FRONT STREET TO WASHINGTON STREET  
 SCALE: VERT.  
 HORIZ.  
 DATE: 01-31-08  
 DRAWN BY: DVH  
 CHECKED BY: JGB