F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
34	95-05109-00-BR	MENARD	14	11
		CONTRACT NO. 93460		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

545 540 535

8+00.00

542.71 C - 22 F - 59

PR ROW — EX ROW — EX ROW — PR ROW

536.50 — 535.12

COMMERCIAL ENTRANCE

543.09

PR ROW — EX ROW

C NEW 18"Ø X 46' PIPE
CULVERTS CLASS D, TYPE 1
INLET - EL. 539.7
(22.4' LT. STA. 7+57)
OUTLET - EL. 536.3
(30.2' LT. STA. 8+03)

EMBANKMENT - 24 CU. YDS.

7+75.00

543.63 C - 28 F - 10

PR ROW — EX ROW — EX ROW — PR ROW

540.25 — 538.71

7+50.00

COMMERCIAL ENTRANCE

544.34

PR ROW — EX ROW — EX ROW — PR ROW

#10%

C NEW 18"Ø X 46' PIPE
CULVERTS CLASS D, TYPE 1
INLET - EL. 541.8
(21' RT. STA. 7+07)
OUTLET - EL. 538.5
(27.4' RT. STA. 7+53)

EMBANKMENT - 0 CU. YDS.

7+25.00

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

FILE NAME = #FILE1#	USER NAME = #USER#	DESIGNED -	REVISED -
		DRAWN	REVISED -
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -
	PLOT DATE = #DATE#	DATE -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

CROSS SECTIONS

SCALE: 1" = 5' | SHEET NO. 10 OF 14 SHEETS | STA. 7+25.00 | TO STA. 8+00.00

BY	DATE
ORIGINAL SURVEYED	
FINAL SURVEY	
NOTE BOOK	
TEMPLATE	
AREAS	
NO.	CROSS CHECKED