

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8047	96-00379-00-PV	SANG	66	10
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LINE NUMBER	PRECAST CONCRETE BOX			STORM SEWERS							BACKFILL
	PCBC 3X2	PCBC 4X2	PCBC 5X3	STORM SEW WM REQ 12	STORM SEW WM REQ 15	STORM SEW WM REQ 18	STORM SEW WM REQ 30	STORM SEW WM REQ 8	SS 1 RCEP S30 R19	TRENCH BACKFILL	
101				35						6.79	
103						217				55.6	
104						174				66.6	
105						168				55.8	
106						123				34.6	
107						73				7.67	
108						8				0.21	
110				10						1.32	
111				2						0.26	
112				14						1.32	
113				128						8.45	
114					21						
115					9						
117				13						0.26	
119				16						0.26	
120				2						0.26	
121				7						0.77	
122				8						0.54	
124				2						0.26	
125				8						0.26	
127				8						0.83	
128				24						4.66	
129				33						8.48	
130				24						3.17	
131				63						8.32	
132					6					0.24	
134				22						2.9	
135				22						2.9	
136				63						8.32	
137				6						0.26	
140							226				
157							216			23.2	
23B				6							
23							93			3.6	
159A				17							
158					129					8.9	
159							11				
158A				5							
SUBTOTAL	0	0	0	533	41	892	546	0	0	317	

LINE NUMBER	PRECAST CONCRETE BOX			STORM SEWERS							BACKFILL
	PCBC 3X2	PCBC 4X2	PCBC 5X3	STORM SEW WM REQ 12	STORM SEW WM REQ 15	STORM SEW WM REQ 18	STORM SEW WM REQ 30	STORM SEW WM REQ 8	SS 1 RCEP S30 R19	TRENCH BACKFILL	
201				18						1.72	
202				61						7.26	
203				31						9.25	
204									95	32.8	
205									59	18.3	
206-213	435									344	
214-215		133								163	
216-220			388							605	
222				10						2.15	
223				72						9.5	
224					11					2.54	
225						55				5.78	
226				2						0.35	
227				11						1.94	
227A				2						0.26	
228				52						6.86	
229				2						0.43	
230				53						7.52	
231				2						0.26	
233				53						7.52	
234				2						0.26	
236				2						0.26	
238				12						1.94	
239				52						6.86	
240				2						0.26	
242				52						6.86	
243				2						0.26	
245				52						6.86	
SUBTOTAL	435	133	388	545	11	55	0	0	154	1250	

LINE NUMBER	PRECAST CONCRETE BOX			STORM SEWERS							BACKFILL
	PCBC 3X2	PCBC 4X2	PCBC 5X3	STORM SEW WM REQ 12	STORM SEW WM REQ 15	STORM SEW WM REQ 18	STORM SEW WM REQ 30	STORM SEW WM REQ 8	SS 1 RCEP S30 R19	TRENCH BACKFILL	
246				2						0.26	
248				4						0.69	
250				12						2.69	
251				52						6.86	
252				2						0.26	
254A								17			
254				12						3.07	
255				52						9	
256				2						0.3	
258				3						0.96	
260							10			5.14	
261							54			10.4	
262				2						0.77	
265				55						15.4	
266				69							
268				20						3.07	
269				83						11	
270				52						7.9	
271				18						2.74	
SUBTOTAL	0	0	0	438	0	0	64	17	0	80.1	
TOTALS	435	133	388	1516	52	947	610	17	154	1647	