

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	7
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

## SCHEDULE OF QUANTITIES

TREE REMOVAL (UNIT)		
LOCATION	20100110 (6 TO 15 UNITS DIA.)	20100210 (OVER 15 UNITS DIA.)
STA. 15+35, 31' RT.		30
STA. 16+82, 39' RT.		30
STA. 20+08, 37' LT.	6	
STA. 20+08, 28' LT.	12	
STA. 20+14, 39' LT.	12	
STA. 20+19, 29' LT.	12	
STA. 20+22, 37' LT.	12	
STA. 20+28, 28' LT.	12	
STA. 24+56, 40' LT.		18
STA. 28+87, 35' LT.	15	
STA. 28+96, 42' LT.	15	
STA. 31+86, 18' LT.		18
STA. 32+04, 14' LT.		18
STA. 32+57, 11' LT.		24
STA. 32+72, 14' LT.		24
STA. 32+80, 21' LT.	12	
STA. 33+19, 20' LT.		24
STA. 33+51, 19' LT.	12	
STA. 34+05, 24' LT.		24
STA. 35+53, 28' LT.		18
STA. 35+99, 16' LT.	12	
STA. 36+10, 16' LT.	12	
STA. 36+18, 10' LT.		24
STA. 36+44, 16' LT.	12	
STA. 36+77, 53' LT.	12	
STA. 36+91, 40' LT.	12	
STA. 43+62, 39' LT.	10	
STA. 43+68, 31' LT.	10	
STA. 44+08, 41' LT.	10	
STA. 44+25, 36' LT.	12	
STA. 44+29, 54' LT.	8	
STA. 44+55, 45' LT.	12	
STA. 44+56, 38' LT.	10	
STA. 44+57, 43' LT.	6	
STA. 44+63, 39' LT.	12	
STA. 44+90, 34' LT.	8	
STA. 45+02, 33' LT.	8	
STA. 46+15, 53' LT.	15	
STA. 46+41, 39' LT.	6	
STA. 46+43, 41' LT.	6	
STA. 46+50, 60' LT.	6	
STA. 46+60, 51' LT.	6	

TREE REMOVAL (UNIT)		
LOCATION	20100110 (6 TO 15 UNITS DIA.)	20100210 (OVER 15 UNITS DIA.)
STA. 46+62, 44' LT.	10	
STA. 46+73, 36' LT.	6	
STA. 49+25, 36' LT.		24
STA. 52+00, 46' LT.		24
STA. 52+06, 63' LT.	8	
STA. 52+07, 45' LT.		24
STA. 52+18, 54' LT.	12	
STA. 52+32, 39' LT.	8	
STA. 52+41, 47' LT.		18
STA. 52+46, 39' LT.	8	
STA. 52+59, 39' LT.	15	
STA. 53+25, 44' LT.	15	
STA. 54+02, 41' LT.		18
STA. 54+23, 35' LT.	15	
STA. 54+48, 24' LT.		24
STA. 54+90, 17' LT.	10	
STA. 55+11, 26' LT.	10	
STA. 55+38, 21' LT.	8	
STA. 55+65, 11' LT.		30
STA. 56+11, 153' RT.		20
STA. 56+13, 161' RT.		18
STA. 56+15, 151' RT.		30
STA. 56+18, 158' RT.		24
STA. 56+28, 116' RT.		18
STA. 56+44, 182' RT.		18
STA. 56+48, 173' RT.		30
STA. 56+70, 127' RT.	6	
STA. 56+82, 187' RT.	10	
STA. 56+84, 21' LT.		24
STA. 56+99, 1' LT.	8	
STA. 56+99, 101' RT.		36
STA. 57+02, 32' LT.		18
TOTAL	474	650

EARTHWORK SCHEDULE				
LOCATION	20200100 EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE (+) OR SHORTAGE (-) (CU YD)
<b>EAST LAKE SHORE DRIVE</b>				
STA. 9+00 TO STA. 14+50	599	449	690	-241
STA. 14+50 TO STA. 20+00	1,037	778	460	318
STA. 20+00 TO STA. 25+50	1,143	857	453	404
STA. 25+50 TO STA. 31+00	2,603	1,952	338	1,614
STA. 31+00 TO STA. 36+70	2,550	1,913	385	1,528
STA. 36+70 TO STA. 42+00	1,393	1,045	1,092	-47
STA. 42+00 TO STA. 47+50	1,706	1,280	1,045	235
STA. 47+50 TO STA. 53+00	1,471	1,103	1,585	-482
STA. 53+00 TO STA. 58+50	3,561	2,671	604	2,067
STA. 58+50 TO STA. 64+00	4,020	3,015	1,363	1,652
STA. 64+00 TO STA. 67+50	168	126	760	-634
<b>ROCHESTER ROAD</b>				
STA. 97+39 TO STA. 101+00	1,093	820	168	652
STA. 101+00 TO STA. 106+50	1,384	1,038	1,074	-36
STA. 106+50 TO STA. 109+95	71	53	122	-69
<b>LACONWOOD DRIVE</b>				
STA. 400+24 TO STA. 400+97	114	86	0	86
<b>SERVICE ENTRANCE</b>				
STA. 200+24 TO STA. 201+42	69	52	4	48
TOTAL	22,982	17,237	10,143	7,094

TREE REMOVAL SCHEDULE (ACRE)	
LOCATION	TREE REMOVAL (ACRE)
<b>EAST LAKE SHORE DRIVE</b>	
STA. 12+80 TO STA. 14+60, LT.	0.2
STA. 38+40 TO STA. 39+90, LT.	0.2
STA. 49+20 TO STA. 52+10, LT.	0.3
TOTAL	0.7

**ie**  
consultants

IE CONSULTANTS, INC.  
6420 SOUTH SIXTH STREET  
SPRINGFIELD, ILLINOIS 62712  
TEL. (217) 529-8027  
FAX (217) 529-4543  
IESPRINGFIELD@IE-CONSULTANTS.COM  
WWW.IE-CONSULTANTS.COM

**SCHEDULE OF QUANTITIES**

DESIGNED BY: JEB	DRAWN BY: AAD	CHECKED BY: CMS	DATE: 4/4/08
---------------------	------------------	--------------------	-----------------

4/9/2008