

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	8
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

DRAINAGE REMOVAL SCHEDULE

STATION	REMOVING INLETS (EACH)	STORM SEWER REMOVAL 12" (FOOT)	STORM SEWER REMOVAL 15" (FOOT)	END SECTIONS TO BE REMOVED (EACH)	WATER VALVES TO BE ADJUSTED (EACH)
EAST LAKE SHORE DRIVE					
STA. 12+00, LT.					1
STA. 17+36, LT.					1
STA. 28+59 TO STA. 30+00, RT.			145		
STA. 30+00, RT.	1				
STA. 30+00 TO STA. 31+00, RT.			100		
STA. 31+00, RT.	1				
STA. 31+00 TO STA. 32+50, RT.			150		
STA. 32+50, RT.				1	
STA. 35+75, RT.				1	
STA. 35+75 TO STA. 37+07, RT.		126			
STA. 39+28 TO STA. 41+00, RT.		172			
STA. 41+00, RT.	1				
STA. 45+46 TO STA. 46+68, RT.			122		
STA. 49+00, RT.				1	
STA. 49+00 TO STA. 51+04, RT.		204			
STA. 51+04 TO STA. 53+25, RT.		215			
STA. 53+25, RT.				1	
TOTALS					

SCHEDULE OF QUANTITIES

REMOVAL SCHEDULE

STATION	CURB REMOVAL (FOOT)	GUTTER REMOVAL (FOOT)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	SIDEWALK REMOVAL (SQ FT)
EAST LAKE SHORE DRIVE				
STA. 10+00, LT.			6	
STA. 10+00, RT.	13			68
BRITTANY LANE				
STA. 300+00 TO STA. 300+59		90		
LACONWOOD DRIVE				
STA. 400+00 TO 400+98		223		
BUCKEYE DRIVE				
STA. 500+38 TO STA. 500+62	50			
STA. 500+00 TO STA. 500+88		71		
TOTALS	63	384	6	68

FENCE AND GUARDRAIL SCHEDULE

STATION	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARDRAIL, TYPE A (FOOT)	REMOVE AND RESET FENCE (FOOT)
EAST LAKE SHORE DRIVE		
STA. 10+00, RT.	25	
STA. 13+82 TO STA. 14+35, RT.		50
TOTALS	25	50

PIPE CULVERT REMOVAL SCHEDULE

STATION	PIPE CULVERT REMOVAL (FOOT)
EAST LAKE SHORE DRIVE	
RT. STA. 11+11	40
RT. STA. 14+49	36
LT. STA. 15+21	43
LT. STA. 17+02	22
RT. STA. 17+09	49
LT. STA. 21+23	53
RT. STA. 21+28	36
STA. 24+45	41
STA. 28+50	46
LT. STA. 29+64	106
STA. 37+07	53
STA. 39+25	56
RT. STA. 41+30	48
LT. STA. 42+36	108
RT. STA. 44+94	50
STA. 46+50	46
STA. 51+00	84
LT. STA. 53+49	23
LT. STA. 54+70	24
RT. STA. 55+52	31
RT. STA. 58+00	92
STA. 61+25	78
STA. 63+25	84
ROCHESTER ROAD	
LT. STA. 104+15	31
LT. STA. 105+56	68
TOTAL	1,348

ENTRANCE SCHEDULE

STATION	ENTRANCE TYPE	INCIDENTAL BITUMINOUS SURFACING (TON)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	AGGREGATE BASE COURSE TYPE A 8" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	TEMPORARY ACCESS (PRIVATE ENTRANCE) (EACH)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) (EACH)
RT. STA. 11+11	C.E.	12	87	77	22		1
LT. STA. 12+74	SERV. DR.	75		479	135		1
RT. STA. 14+49	C.E.	21	137	130	37		1
LT. STA. 15+21	P.E./MBTO	9	106	57	16	1	
LT. STA. 17+02	C.E.	10	130	60	17		1
RT. STA. 17+09	P.E./MBTO	15	97	96	27	1	
RT. STA. 17+81	C.E.	7	52	47	14		1
RT. STA. 21+28	C.E.	25	135	160	45		1
RT. STA. 33+50	C.E.	23	118	148	42		1
RT. STA. 41+02	C.E.	19	63	129	37		1
RT. STA. 43+08	C.E.	18	50	114	32		1
LT. STA. 43+18	MBTO	3		20	6		
LT. STA. 44+62	MBTO	3		18	6		
RT. STA. 44+94	C.E.	17	70	106	30		1
LT. STA. 53+49	P.E./MBTO	9	93	62	18	1	
LT. STA. 54+68	P.E./MBTO	10		67	19	1	
RT. STA. 55+52	C.E.		190				1
RT. STA. 56+62	SERV. DR.	136		852	239		1
RT. STA. 57+56	C.E.		568				1
LT. STA. 57+72	MBTO	3		18	6		
LT. STA. 104+17	P.E.	10		62	18	1	
LT. STA. 105+54	P.E.	11	57	74	21	1	
RT. STA. 55+50 TO STA. 56+50	BIKE TRAIL	21		141	40		
TOTALS	TOTALS	457	1,953	2,917	827	6	13

SEEDING SCHEDULE

STATION TO STATION	SEEDING CLASS 2 (ACRE)	NITROGEN (POUND)	PHOSPHORUS (POUND)	POTASSIUM (POUND)	AGRICULTURAL GROUND LIMESTONE (TON)	MULCH, METHOD 2 (TON)	TEMPORARY EROSION CONTROL SEEDING (POUND)	
EAST LAKE SHORE DRIVE								
9+00	14+50	0.43	39	39	39	0.86	0.86	129
14+50	20+00	0.37	34	34	34	0.74	0.74	111
20+00	25+50	0.41	37	37	37	0.82	0.82	123
25+50	31+00	0.62	56	56	56	1.24	1.24	186
31+00	36+70	0.69	63	63	63	1.38	1.38	207
36+70	42+00	0.58	53	53	53	1.16	1.16	174
42+00	47+50	0.59	54	54	54	1.18	1.18	177
47+50	53+00	0.52	47	47	47	1.04	1.04	156
53+00	58+50	1.09	99	99	99	2.18	2.18	327
58+50	64+00	1.31	118	118	118	2.62	2.62	393
64+00	67+50	0.40	36	36	36	0.80	0.80	120
SUB-TOTAL ELSD		7.01	636	636	636	14	14	2,103
ROCHESTER ROAD								
101+00	106+50	0.76	69	69	69	1.52	1.52	228
106+50	109+95	0.14	13	13	13	0.28	0.28	42
SUB-TOTAL RR		0.90	82	82	82	2	2	270
TOTAL (ALL ROADS)		8.0	720	720	720	16	16	2,373

ie CONSULTANTS, INC.
 6420 SOUTH SIXTH STREET
 SPRINGFIELD, ILLINOIS 62712
 TEL: (217) 529-8927
 FAX: (217) 529-4543
 IESPRINGFIELD@IE-CONSULTANTS.COM
 WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DESIGNED BY: JEB	DRAWN BY: AAD	CHECKED BY: CMS	DATE: 4/4/08
---------------------	------------------	--------------------	-----------------