

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	12
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

## SCHEDULE OF QUANTITIES

EROSION CONTROL SCHEDULE							
STATION	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	STONE DUMPED RIPRAP CLASS B3	STONE DUMPED RIPRAP CLASS B4	FILTER FABRIC	REMOVE EXISTING RIPRAP
	(EACH)	(FOOT)	(EACH)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
<b>EAST LAKE SHORE DRIVE</b>							
STA. 58+14 TO STA. 64+00, LT.		564					
STA. 59+00, RT.	1						
STA. 59+10, LT.	1						
STA. 59+90, LT.	1						
STA. 61+00, LT.			2				
STA. 61+00, RT.	1						
STA. 61+30, LT.	1						
STA. 61+30, LT.	1						
STA. 61+60, RT.	1				17	17	
STA. 62+00 TO STA. 64+00, RT.		210					
STA. 62+02, RT.				3		3	
STA. 62+70, LT.	1						
STA. 63+00, RT.	1				4	4	
STA. 63+25, RT.	1						
STA. 63+50, LT.	1						
STA. 63+50, RT.	1						
STA. 63+68, LT.			1				
STA. 64+00, RT.	1						
STA. 64+00 TO STA. 67+50, LT.		360					
STA. 64+00 TO STA. 67+50, RT.		354					
STA. 64+10, LT.	1						
STA. 64+55, RT.	1						
STA. 64+65, LT.	1						
STA. 65+00, LT.	1						
STA. 65+00, RT.	1						
STA. 66+00, LT.	1						
STA. 66+00, RT.	1						
<b>SUB-TOTAL EAST LAKE SHORE DRIVE</b>	<b>52</b>	<b>6,716</b>	<b>14</b>	<b>6</b>	<b>31</b>	<b>37</b>	<b>10</b>
<b>ROCHESTER ROAD</b>							
STA. 101+06 TO STA. 103+90, RT.		328					
STA. 102+00, LT.	1						
STA. 102+00, RT.	1						
STA. 104+00, LT.	1						
STA. 104+00, RT.	1						
STA. 104+31, LT.			1				
STA. 105+71, LT.			1				
<b>SUB-TOTAL ROCHESTER ROAD</b>	<b>4</b>	<b>328</b>	<b>2</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
<b>OVERALL TOTAL</b>	<b>56</b>	<b>7,044</b>	<b>16</b>	<b>6</b>	<b>31</b>	<b>37</b>	<b>10</b>

	IE CONSULTANTS, INC. 6420 SOUTH SIXTH STREET SPRINGFIELD, ILLINOIS 62712 TEL. (217) 529-8027 FAX (217) 529-4543 IESPRINGFIELD@IE-CONSULTANTS.COM WWW.IE-CONSULTANTS.COM
	SCHEDULE OF QUANTITIES

DESIGNED BY:	DRAWN BY:	CHECKED BY:	DATE:
JEB	AAD	CMS	4/4/08