93467

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	14
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

PIPE & STRUCTURE NUMBERS	PIPE LOCATION	STANDARD NUMBER	TRENCH BACKFILL CU. YD.	STORM SEWERS FOOT CLASS A TYPE 1 12"	15"	18"	30"	TYPE 2 12"	15"	24"	30"	PIPE CULVERTS FOOT CLASS A TYPE 1 15"	24"	TYPE 2 30"	PIPE CULVERTS FOOT CLASS A TYPE 1 EQRS 42"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	15"	18"	24"	30"	EQRS 42"	INLETS TYPE A TYPE 3V F & G	CATCH BASIN TYPE C TYPE 8 GRATE	RD CATCH BASIN 3' DIA. TYPE 3V F & G	RD MANHOLES 4' DIA TYPE 3V F & G	RD MANHOLES 5' DIA TYPE 3V F & G	RD MANHOLES 4' DIA TYPE 1 CLID	INLETS TO BE ADJUSTED	REMOVING MANHOLES	MANHOLES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3V F & G	REMOVE & RE-INSTALL CONCRETE FLARED END SECTIONS
P-33	S-39 TO S-38					53																									
S-39	STA. 30+50, RT	602306 604091																					1								
P-34	S-40 TO S-39			34																											
S-40	STA. 30+85, RT	602306 604091																					1								
P-45	S-49 TO S-40			82																											
S-49	STA. 31+70, RT	602306 604091																					1								
P-46	S-50 TO S-49			84																											
S-50	STA. 32+55, RT	602301 604091																				1									
S-51	STA. 35+15, RT	602301 604091																				1									
P-47	S-51 TO S-52			50																											
S-52	STA. 35+15, LT	602306 604091																					1								
P-48	S-52 TO S-54			8																											
S-54	STA. 35+15, LT	542301															1														
S-53	STA. 36+50, LT																					1									
P-49	S-53 TO S-55			11																											
S-55	STA. 36+50, LT	542301															1														
S-56A	STA. 37+07, RT																													1	
P-51	S-56 TO S-56A						1																								
S-56	STA. 37+07, RT	602401 604091																													
P-50	S-57 TO S-56						61																								
S-57	STA. 37+07, LT	542301																			1										
S-58	STA. 38+05, RT	602301 604091																				1									
P-52	S-58 TO S-59			45																											
S-59	STA. 38+50, RT	602306 604091																					1								
P-53	S-59 TO S-60			15																											
S-60	STA. 38+65, RT	602306 604091																					1								
P-54	S-60 TO S-58A			65																											
S-58A	STA. 39+31, RT																													1	
P-56	S-61 TO S-58A						3																								
S-61	STA. 39+30, RT																							1							
P-55	S-62 TO S-61						78																								
S-62	STA. 39+25, LT																				1										
S-63	STA. 40+85, RT																					1									
P-57	S-63 TO S-64			8																											
S-64	STA. 40+85, RT																														
	STA. 41+00, RT																														1
S-68	STA. 45+70, RT																					1									
P-59	S-68 TO S-69			4																											
S-69	STA. 45+70, RT																										1				
S-70	STA. 46+40, LT																														
P-60	S-70 TO S-71								72																						
S-71	STA. 46+68, RT																														1
P-61	S-75 TO S-71				118																										
S-75	STA. 47+88, RT																							1							
P-64	S-76 TO S-75			15																											
S-76	STA. 48+03, RT																							1							

ie consultants

IE CONSULTANTS, INC.
6420 SOUTH SIXTH STREET
SPRINGFIELD, ILLINOIS 62712
TEL. (217) 529-8027
FAX (217) 529-4543
IESPRINGFIELD@IE-CONSULTANTS.COM
WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DESIGNED BY:	DRAWN BY:	CHECKED BY:	DATE:
JEB	AAD	CMS	4/4/08

4/18/2008

g:\S842\CAD\Roadway\842sch09.dgn