

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	WABASH	36	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• (12Z,12,13)RS-3

PAVEMENT MARKING SCHEDULE

STATION	STATION	LENGTH FEET	SHORT TERM PAVEMENT MARKING FT.	WORK ZONE PAVEMENT MARKING REMOVAL SQ. FT.	TEMPORARY PAVEMENT MARKING LINE 4" FT.	TEMPORARY PAVEMENT MARKING LINE 6" FT.	TEMPORARY PAVEMENT MARKING LINE 24" FT.	PAINT PAVEMENT MARKING - LINE 4" FT.	THERMOPLASTIC PAVEMENT MARKING - LINE 4" FT.	THERMOPLASTIC PAVEMENT MARKING - LINE 6" FT.	THERMOPLASTIC PAVEMENT MARKING - LINE 24" EACH	RAISED REFLECTIVE PAVEMENT MARKER EACH	
0+00.00	TO 5+70.50	570.5	171.2	19.0	142.6				143			7	
5+70.50	TO 6+00.12	29.6	8.9	1.0	7.4				7			0	
6+00.12	TO 6+30.12	30.0	9.0	1.0	7.5				8			0	
6+30.12	TO 8+43.87	213.8	0.0	0.0	53.4				53			3	
8+43.87	TO 8+73.87	30.0	9.0	1.0	7.5				8			0	
8+73.87	TO 9+03.50	29.6	8.9	1.0	7.4				7			0	
9+03.50	TO 19+27.60	1,024.1	307.2	34.1	256.0	112	27		256	112	27	13	
0+00.00	TO 9+61.29	961.3	288.4	32.0	240.3				240			12	
9+62.40	TO 15+84.11	621.7	186.5	20.7	155.4				155			8	
15+84.11	TO 16+14.11	30.0	9.0	1.0	67.5				68			0	
16+14.11	TO 16+34.00	19.9	6.0	0.7	44.8				45			0	
16+34.00	TO 42+64.10	2,630.1	789.0	87.7	7,870.1				7870			33	
43+05.55	TO 88+64.07	4,558.5	1,367.6	152.0	11,055.7				11056			57	
88+59.07	TO 90+78.00	218.9	65.7	7.3	611.5				612			3	
90+78.00	TO 134+34.00	4,356.0	1,306.8	145.2	11,545.0			11,545.0				55	
134+34.00	TO 134+64.00	30.0	9.0	1.0	67.5				67.5			0	
134+64.00	TO 136+36.00	172.0	0.0	0.0	387.0			387.0				2	
136+36.00	TO 136+66.00	30.0	9.0	1.0	67.5			67.5				0	
136+66.00	TO 192+98.80	5,632.8	1,689.8	187.8	12,414.8			12,414.8				70	
198+81.40	TO 220+37.90	2,156.5	647.0	71.9	4,852.1			4,852.1				27	
220+37.90	TO 220+38.90	1.0	0.3	0.0	2.3			2.3				0	
220+67.00	TO 220+70.00	3.0	0.9	0.1	6.8			6.8				0	
220+70.00	TO 221+00.00	30.0	9.0	1.0	0.5			0.5				0	
221+00.00	TO 235+00.00	1,400.0	420.0	46.7	3,055.0			3,055.0				18	
235+00.00	TO 235+30.00	30.0	9.0	1.0	34.5			34.5				0	
235+30.00	TO 250+22.90	1,492.9	447.9	49.8	3,296.0			3,296.0				19	
250+23.30	TO 414+19.30	16,396.0	4,918.8	546.5	36,579.0			36,579.0				205	
414+21.60	TO 429+94.10	1,572.5	471.8	52.4	3,480.1			3,480.1				20	
429+95.80	TO 434+70.00	474.2	142.3	15.8	1,067.0			1,067.0				6	
434+70.00	TO 435+00.00	30.0	9.0	1.0	67.5			67.5				0	
435+00.00	TO 445+50.00	1,050.0	315.0	35.0	2,234.5	70		2,234.5		70		13	
445+50.00	TO 445+80.00	30.0	9.0	1.0	67.5			67.5				0	
445+80.00	TO 467+07.40	2,127.4	638.2	70.9	4,719.7			4,719.7				27	
467+00.00	TO 475+60.71	860.7	258.2	28.7	1,936.6			1,936.6				11	
475+60.78	TO 483+38.55	777.8	233.3	25.9	1,749.9			1,749.9				10	
483+39.22	TO 517+12.28	3,373.1	1,011.9	112.4	7,839.7			7,839.7				42	
516+92.49	TO 542+05.82	2,513.3	754.0	83.8	6,375.5			6,375.5				31	
543+18.51	TO 588+96.50	4,578.0	1,373.4	152.6	12,835.0			12,835.0				57	
589+00.00	TO 600+16.83	1,116.8	335.0	37.2	2,512.9			2,512.9				14	
600+16.83	TO 600+46.83	30.0	9.0	1.0	67.5			67.5				0	
PROJECT TOTALS			61,232	18,254	2,028	137,789	182	27	117,261	20,527	182	27	766

PLOT DATE = 3/28/2007
 FILE NAME = c:\projects\94984\081703\pl.dgn
 USER NAME = amsrzn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____