

# SUMMARY OF QUANTITIES

SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9392	05-00024-00-PV	MADISON	81	3
STA.		TO STA.		

CONTRACT NO. 97347

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	56
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	96
20200100	EARTH EXCAVATION	CU YD	5,649
20800150	TRENCH BACKFILL	CU YD	779
25000210	SEEDING, CLASS 2A	ACRE	1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
25100115	MULCH, METHOD 2	ACRE	1
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	1
28000500	INLET AND PIPE PROTECTION	EACH	74
28100105	STONE RIPRAP, CLASS A3	SQ YD	5
28200200	FILTER FABRIC	SQ YD	5
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	10,325
30201500	LIME	TON	199
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	10,325
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	480
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	1,188
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	350
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	350
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	626
40800030	AGGREGATE (PRIME COAT)	TON	3
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	261
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	7,639
42000800	HIGH-EARLY STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	899
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,050
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	23,026
42400800	DETECTABLE WARNINGS	SQ. FT.	280
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,062
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	663
44000600	SIDEWALK REMOVAL	SQ FT	7,404
44201721	CLASS D PATCHES, TYPE III, 6"	SQ YD	21
50105220	PIPE CULVERT REMOVAL	FOOT	2,084
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	697
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	205
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	40
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	26
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,442
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	151
550B0090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	533
550B0120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	78

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	2
60235300	INLETS, TYPE A, TYPE 1 FRAME AND CLOSED LID	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6
60240215	INLETS, TYPE B, TYPE 1 FRAME AND CLOSED LID	EACH	1
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	8
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	5
60240327	INLETS, TYPE B, TYPE 23 FRAME AND GRATE	EACH	2
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	12
60242500	INLETS, SPECIAL, NO. 1	EACH	19
60242600	INLETS, SPECIAL, NO. 2	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	7
60500060	REMOVING INLETS	EACH	9
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,215
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	331
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5,078
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	620
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	178
X5420350	END SECTIONS, 18" SPECIAL	EACH	1
X7010010	TRAFFIC CONTROL - STAGE I	L SUM	1
X7010020	TRAFFIC CONTROL - STAGE II	L SUM	1
X7010030	TRAFFIC CONTROL - STAGE III	L SUM	1
XX002053	LANDSCAPE RESTORATION	L SUM	1
XX001484	ROOF DRAIN GUTTER OUTLET	EACH	12
XX003360	STORM SEWERS, PVC SDR 26, 12"	FOOT	484
XX005635	STORM SEWERS, PVC SDR 26, 15"	FOOT	265
XX006204	STORM SEWERS, PVC SDR 26, 24"	FOOT	48
XZ127900	RETAINING WALL REMOVAL	FOOT	10
Z0012450	CONCRETE STEPS	CU YD	1
Z0041600	PLUG EXISTING INLET	EACH	1
XX003571	STORM SEWERS, PVC SDR 26, 18"	FOOT	64
XX007447	STORM SEWERS, PVC SDR 26, 36"	FOOT	117

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES

NORTH STAUNTON ROAD IMPROVEMENTS  
CITY OF TROY  
MADISON COUNTY, ILLINOIS

P:\030131.dwg\030131SUMMARY.dwg 2/1/2008 2:14:00 PM CST