

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	102RS-4	PERRY	13	8
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				

### MAINLINE RESURFACING SCHEDULE

#### MAINLINE RESURFACING SCHEDULE

LOCATION STATION	STATION TO	LENGTH (FT)	ROADWAY WIDTH (FT)	ROADWAY AREA (SQ YD)	HMA SURF. REM. 3/4"	HMA SURF. REM. - BUTT JT.	TEMPORARY RAMP	HMA SURF. CSE. MIX C. N90	LEVELING BINDER (MM), N90	BIT. MAT. (PRIME COAT)	AGG. (PRIME COAT)	AGG. SHOULDER TYPE B
					(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(GAL)	0	(TON)
STA. 334+93 TO STA. 510+15												
	334+93.00 TO 335+23.00	30.0	26.0	87		87	9	7	4	16	0.3	0.8
	335+23.00 TO 387+12.00	5,189.0	26.0	14,990	14,990			1,262	630	2,698	45.0	130.8
S. N. 073-2005	387+12.00 TO 393+81.00	669.0	26.0	1,933	1,933			163	81	348	5.8	16.9
	393+81.00 TO 509+85.00	11,604.0	26.0	33,523	33,523			2,822	1,408	6,034	100.6	292.5
	509+85.00 TO 510+15.00	30.0	26.0	87		87	9	7	4	16	0.3	0.8
<b>TOTALS</b>		<b>17522.0</b>			<b>50,446</b>	<b>174</b>	<b>18</b>	<b>4,261</b>	<b>2,127</b>	<b>9,111</b>	<b>151.9</b>	<b>441.7</b>

### PAVEMENT MARKING SCHEDULE

STATION TO STATION	PAINT PAVEMENT MARKING			TEMPORARY	NOTES		
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH	4 INCH			
	FOOT	FOOT	FOOT	FOOT			
Station 334+93 To Sta. 510+15							
LT. & RT.	334+93.0 TO 510+15.0			34532	4381	38913	EDGELINE
RT.	334+93.0 TO 339+00.0					407	
LT.	341+00.0 TO 346+60.0					560	
<b>SUB-TOTALS</b>				<b>34532</b>	<b>967</b>	<b>4381</b>	<b>39880</b>
<b>TOTALS</b>					<b>39880</b>		<b>39880</b>

PLOT DATE = 3/13/2008  
 FILE NAME = c:\p\m\m\m\98984\98984.mxd  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = mcdonald