

MULCHING DATA

ALL EARTHEN AREAS WITHIN THE GRADING LIMITS WILL BE MULCHED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS AT THE RATE OF 2 TONS PER ACRE (STRAW) AT THE RATE OF 1.25 TONS PER ACRE (HYDROMULCH).
 AREA TO BE MULCHED 4.0 ACRES
 DATE MULCHING COMPLETED _____

EARTH FILLETS

EARTH FILLETS WILL BE CONSTRUCTED ADJACENT TO ALL PAVEMENT OVERLAY AREAS. THE EARTH FILLETS ARE SHOWN ON THE CROSS-SECTIONS AND THE STAKING PLAN SHEETS AS THE PROPOSED GRADING, SEEDING AND MULCHING LIMITS. A 1-1/2 INCH DROP SHALL BE MAINTAINED FROM THE PAVEMENT EDGE TO THE EARTH SHOULDER. THE EARTH FILLETS WILL NOT REQUIRE COMPACTING OR GRADING, OTHER THAN LIGHT ROLLING AND SHAPING.

SEEDING DATA


THE GRADING LIMITS ARE SHOWN ON THE STAKING PLAN SHEETS BY A HEAVY DASHED LINE (---). ALL AREAS WITHIN THESE LIMITS, EXCEPT THE PROPOSED PAVEMENT, SHALL BE LIMED, FERTILIZED AND SEEDED IN ACCORDANCE WITH THE FOLLOWING FORMULA AND RATES OF APPLICATION.

LIME (TONS PER ACRE)	2
FERTILIZER (MINIMUM POUNDS OF AVAILABLE PLANT FOOD PER ACRE)	
N	90
P2O5	350
K2O	240
TOTAL	680

SEEDING (MINIMUM POUNDS OF PURE LIVE SEED PER ACRE)	
ALTA FESCUE	80
PERENNIAL RYEGRASS	30
CREeping RED FESCUE	20
SPRING OATS	48
AREA TO BE SEEDED	4.0 ACRES
DATE SEEDING COMPLETED	_____

LEGEND

- EXISTING BUILDINGS
- EXISTING IMPROVEMENTS
- PROPOSED IMPROVEMENTS
- PROPOSED FLARED END SECTIONS
- PROPOSED 15" R.C.P.
- EXISTING GRADE
- PROPOSED GRADE



0' 25' 50' 100'
 HALF SIZE SCALE: 1" = 100'
 FULL SIZE SCALE: 1" = 50'

DATE	REVISION	BY

**METROPOLIS MUNICIPAL AIRPORT
 METROPOLIS, ILLINOIS**

ILL. Project No. 07AD128D_0800 Plans No. R-191STK.DWG Scale 1"=50' Date 03/18/08	LAYOUT JAC 03/14/08 DRAWN MDR 03/18/08 REVIEWED CAH xx/xx/xx
---	--



**CONSTRUCT PARTIAL
 PARALLEL TAXIWAY**

PROPOSED
 STAKING
 PLAN

MAY 14, 2008 2:26 PM KIKCA00394 \\AIRPORTS\METROPOLIS\07AD128\CAD\SHEETS\R-191STK.DWG - Layout2

IL PROJ.: M30-3760 A.I.P. PROJ.: 3-17-0067-B9