


REVISIONS

NUMBER	BY	DATE



EARTHWORK SUMMARY

STATION	EXCAVATE END AREA (S.F.)	EMBANK END AREA (S.F.)
4+50.00	0.00	0.00
5+00.00	25.37	0.42
5+50.00	22.72	1.01
6+00.00	20.31	5.58
6+50.00	19.65	9.84
7+00.00	18.48	13.75
7+50.00	17.60	14.56
8+00.00	16.56	14.51
8+50.00	16.43	15.60
9+00.00	16.89	14.74
9+50.00	16.90	12.80
10+00.00	16.66	10.90
10+50.00	17.40	11.57
11+00.00	17.57	13.16
11+50.00	16.91	16.76
12+00.00	16.59	21.45
12+50.00	17.13	21.44
13+00.00	17.18	22.62
13+50.00	14.61	29.55
14+00.00	13.31	39.14
14+50.00	13.54	31.76
15+00.00	14.78	21.62
15+50.00	17.49	6.34
16+00.00	41.28	0.29
16+50.00	31.05	3.76
17+00.00	16.28	15.14
17+50.00	18.23	10.71
18+00.00	18.23	7.42
18+50.00	19.30	5.50
19+00.00	19.70	4.70

EARTHWORK SUMMARY

STATION	EXCAVATE END AREA (S.F.)	EMBANK END AREA (S.F.)
19+50.00	19.14	5.44
20+00.00	18.49	6.08
20+50.00	18.21	9.79
21+00.00	17.43	12.42
21+50.00	17.75	11.96
22+00.00	18.40	10.02
22+50.00	18.90	9.16
23+00.00	18.88	7.52
23+50.00	18.12	9.73
24+00.00	18.20	10.18
24+50.00	19.21	9.91
25+00.00	19.67	7.59
25+50.00	20.01	6.52
26+00.00	20.56	4.38
26+50.00	19.88	5.74
27+00.00	19.68	6.28
27+50.00	18.88	9.76
28+00.00	18.15	10.69
28+50.00	17.06	12.63
29+00.00	17.21	12.81
29+50.00	17.54	12.21
30+00.00	18.64	8.96
30+50.00	18.40	9.17
31+00.00	18.04	9.60
31+50.00	17.77	7.76
32+00.00	18.66	6.85
32+50.00	19.34	9.99
33+00.00	18.70	13.12
33+50.00	17.24	14.21
34+00.00	14.94	17.26

EARTHWORK SUMMARY

STATION	EXCAVATE END AREA (S.F.)	EMBANK END AREA (S.F.)
34+50.00	16.36	15.39
35+00.00	17.17	14.83
35+50.00	17.42	15.76
36+00.00	17.25	15.81
36+50.00	18.37	11.61
37+00.00	18.99	6.06
37+50.00	21.32	4.94
38+00.00	22.58	3.04
38+50.00	20.79	6.14
39+00.00	19.08	10.72
39+50.00	19.88	19.02
40+00.00	19.07	25.51
40+50.00	19.05	32.73
41+00.00	18.30	46.85
41+50.00	19.44	79.21
42+00.00	20.31	29.47
42+50.00	19.84	7.92
43+00.00	19.54	5.89
43+50.00	22.65	2.21
44+00.00	24.02	0.08
44+50.00	22.98	0.46
45+00.00	22.68	6.15
45+50.00	0.00	73.98
46+00.00	0.00	93.10
46+50.00	0.00	75.26
47+00.00	117.54	118.12
47+50.00	205.31	24.30
48+00.00	302.38	0.00
48+50.00	0.00	0.00

SPARTA COMMUNITY AIRPORT
 HUNTER FIELD
 SPARTA, ILLINOIS

WIDEN AND OVERLAY RUNWAY 18/36

EARTHWORK SUMMARY

© Copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 184-000618

DESIGN BY:	KLB
DRAWN BY:	CMT
CHECKED BY:	JEF
APPROVED BY:	JEF
DATE:	03/21/2008
JOB No:	0641203
IL PROJ. NO. SAR-3652	
AIP PROJ. NO. 3-17-0094-B9	
SHEET 17 OF 28 SHEETS	