


90% FED.
10% STATE
LIRBAN

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0014	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4					
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	12	12					
* 72000100	SIGN PANEL - TYPE 1	SO FT	259	229			15	15	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	4	4					
* 72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	198	198					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,695	1,695					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	18,000	18,000					
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	2,600	2,600					
* 78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SO FT	278	278					
* 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	9,915	9,915					
* 78008220	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 5"	FOOT	2,600	2,600					
* 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	678	678					
* 78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	594	594					
* 78008270	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	FOOT	195	195					
* 78100300	REPLACEMENT REFLECTOR	EACH	270	270					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	550	550					
78300100	PAVEMENT MARKING REMOVAL	SO FT	4,991	4,991					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	270	270					
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	237			237			
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	221			221			
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	12			12			
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	6			6			
* 81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24"x24"x10"	EACH	2			2			
X 81300960	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE 42"x36"x12"	EACH	3		3				
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5,982			5,982			

16 * Specialty Items

Rev.

H:\Jobs\2014\20140222\CAD\Site\adgn\00\16045-Summary.dgn 3/27/2014 9:33:34 AM



USER NAME : 0766	DESIGNED - JSJ	REVISED -
PLOT SCALE : 100.0000' / 1" =	DRAWN - HJM	REVISED -
PLOT DATE : 3/21/2014	CHECKED - TNS	REVISED -
	DATE - 03-15-2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

63rd STREET BRIDGE REPLACEMENT - COOK COUNTY
SUMMARY OF QUANTITIES

SCALE: 1"=60' SHEET 4 OF 8 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	1920-B	COOK	142	8
CONTRACT NO. 60J15			ILLINOIS FED. AID PROJECT	