

90% FED.
10% STATE

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0004	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
* X0370123	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	140			140			
* X0370124	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL (CDOT)	FOOT	3,330		320				3,010
* X0370125	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	952			952			
* X0370126	UNIT DUCT, 600 V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE (CDOT)	FOOT	102			102			
* X0370203	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL (CDOT)	FOOT	720		720				
* X0370127	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10 (CDOT)	FOOT	2,786			2,786			
* X0370128	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4 (CDOT)	FOOT	932			932			
* X0370129	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2 (CDOT)	FOOT	2790		290	2,500			
* X0370204	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4 (CDOT)	FOOT	870		870				
* X0370140	REMOVE EXISTING STREET LIGHTING EQUIPMENT (CDOT)	L SUM	1			1			
* X0370205	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 500 MCM (CDOT)	FOOT	2320		2320				
* X0370120	RACK, SECONDARY-AERIAL, 2-WIRE (CDOT)	EACH	1			1			
* X0370131	REMOVE CONDUIT ATTACHED TO STRUCTURE (CDOT)	FOOT	2,403		320	2,083			
* X0370132	MAINTENANCE OF STREET LIGHTING SYSTEM (CDOT)	L SUM	1			1			
* X0370003	ELECTRIC CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GROUND (CDOT)	FOOT	2,692			2,692			
* X0370133	PAINT EXISTING STREET LIGHT/TRAFFIC EQUIPMENT COMPLETE (CDOT)	EACH	1			1			
* X0370134	JUNCTION BOX, POLE OR POST MOUNTED (CDOT)	EACH	2				1	1	
* X0370136	REMOVE EXISTING JUNCTION BOX (CDOT)	EACH	30			30			
* X0370137	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING (CDOT)	L SUM	1			1			
* X0370138	ELECTRIC CABLE IN CONDUIT, COAXIAL VIDEO, RG-59/U (CDOT)	FOOT	197				48	149	
* X0370139	MAINTENANCE OF LIGHTING SYSTEM (CDOT)	CAL MO	6			6			
* X0370084	DRILL MANHOLE OR HANDHOLE (CDOT)	EACH	28				14	14	
* X0370085	CLEAN MANHOLE OR HANDHOLE (CDOT)	EACH	8				4	4	
* X0370076	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (CDOT)	FOOT	456				238	218	
* X0370002	BREAKDOWN STREET LIGHT FOUNDATION (CDOT)	EACH	6				3	3	
* X0370001	TRENCH AND BACKFILL WITH SCREENINGS (CDOT)	FOOT	316				42	39	235
* X0370086	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/4" ANCHOR RODS, 17 1/4" BOLT CIRCLE, 9 FEET (CDOT)	EACH	1					1	

© 100% STATE (NP) * Specialty Items

Rev.

H:\026208\2013022\CA01\Site\Drawings\0016015-Summary.dgn
 3/31/2014 9:14:05 AM

	USER NAME = 0766	DESIGNED - JSJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / 1"	DRAWN - HJM	REVISED -			94	1920-B	COOK	142	10
	CHECKED - TNS	REVISED -		SCALE: NTPSD'	SHEET 6 OF 8 SHEETS	STA.	TO STA.	CONTRACT NO. 60J15		
	PLOT DATE = 3/31/2014	DATE = 03-15-2013	REVISED -	ILLINOIS FED. AID PROJECT						