

90% FED,
10% STATE

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0014	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
* X0370087	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/2" ANCHOR RODS, 16 1/2" BOLT CIRCLE, 11 FEET (CDOT)	EACH	5				3	2	
* X0370088	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION (CDOT)	EACH	2				1	1	
* X0370089	TEMPORARY TRAFFIC SIGNAL INSTALLATION (CDOT)	EACH	2				1	1	
* X0370090	SIGNAL HEAD, POLYCARBONATE, LED, 3-SECTION, BRACKET MOUNTED (CDOT)	EACH	6				3	3	
* X0370091	SIGNAL HEAD, POLYCARBONATE, LED, 3-SECTION, MAST ARM MOUNTED (CDOT)	EACH	10				5	5	
* X0370092	SIGNAL HEAD, POLYCARBONATE, LED, 4-SECTION, BRACKET MOUNTED (CDOT)	EACH	2				1	1	
* X0370093	SIGNAL HEAD, POLYCARBONATE, LED, 4-SECTION, MAST ARM MOUNTED (CDOT)	EACH	2				1	1	
* X0370094	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, 1-FACE, LED, BRACKET MOUNTED, COUNTDOWN (CDOT)	EACH	4				2	2	
* X0370095	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, 2-FACE, LED, BRACKET MOUNTED, COUNTDOWN (CDOT)	EACH	4				2	2	
* X0370096	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 9/C (CDOT)	FOOT	1,086				552	534	
* X0370097	MAST ARM, STEEL, MONOTUBE, 30 FOOT (CDOT)	EACH	1					1	
* X0370098	MAST ARM, STEEL, MONOTUBE, 35 FOOT (CDOT)	EACH	2				1	1	
* X0370099	MAST ARM, STEEL, MONOTUBE, 40 FOOT (CDOT)	EACH	1					1	
* X0370100	MAST ARM, STEEL, MONOTUBE, 44 FOOT (CDOT)	EACH	2				2		
* X0370101	POLE, STEEL, ANCHOR BASE, 11" DIAMETER, 3 GAUGE, 32'-6" (CDOT)	EACH	2				1	1	
* X0370102	POLE, STEEL, ANCHOR BASE, 11" DIAMETER, 3 GAUGE, 34'-6" (CDOT)	EACH	1					1	
* X0370103	POLE, STEEL, ANCHOR BASE, 12 1/2" DIAMETER, 3 GAUGE, 34'-6" (CDOT)	EACH	5				3	2	
* X0370104	RELOCATE EXISTING VIDEO DETECTION CAMERA, COMPLETE (CDOT)	EACH	2				1	1	
* X0370105	REMOVE EXISTING TRAFFIC SIGNAL POST OR POLE (CDOT)	EACH	8				4	4	
* X0370106	REMOVE CABLE FROM CONDUIT (CDOT)	FOOT	4426		3360		539	527	
* X0370107	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT (CDOT)	EACH	2				1	1	

*Specialty Items

Rev.

H:\Jobs\2014\2014022\CA0\Site\Drawings\00_0160_05-Summary.dgn 3/31/2014 9:34:52 AM

<p>201 W. Higgins Road, Suite 200 Chicago, Illinois 60631 773.599.012</p>	USER NAME : 0766	DESIGNED - JSO	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES</p>			F.A.I. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * 100.0000 / in	DRAWN - HJM	REVISED -					94	1920-B	COOK	142	11
	PLOT DATE * 3/31/2014	CHECKED - TNS	REVISED -					CONTRACT NO. 60J15				
	DATE - 03-15-2013	REMOVED -	REVISED -					ILLINOIS FED. AID PROJECT				

SCALE: NTS&O' SHEET 7 OF 8 SHEETS STA. TO STA.